

SURVEY & REMONUMENTATION

1993

COMMISSION

**Barry County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

May 14 11 08 AM '93

Sandy Schondelmar
REGISTER OF DEEDS

002001

Register of Deeds Stamp & File Number

For corners in

<u>Barry</u> (County)	Located in:	Corner Code #
	2N 10W	D-6 (C 1/4, 17) Orangeville Twp.
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	▲	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche in a field survey on January, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 D-6 MDNR 1947 Ratekin 10/82
 Found iron 3' below surface of road Found MDNR mon. 1.5' deep
 Set 4" x 60" conc. post with brass E edge of bit.
 plate 8" above ground PK NW side PP S 60° W 96.11'
 No wit. given; no meas. N or W PK W side 40" Oak S 10° W 90.07'
 1986 Jonker meas. N 2645.40'; PK W side 40" Oak N 45° E 32.81'
 W 2635.04'; found R. Moored C/L st. sign post N 85° E 12.45'
 capped iron C/L Marsh Rd. W 11.0'
 On C/L Saddler Rd. West

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 D-6 Found rerod with cap in mon. As per above wit.
 box PP no PK found
 On C/L bit. North extended South,
 C/L bit. N-S, W 11'±
 On C/L gravel West
 C/L 2 track E is N 15'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 D-6 Capped rerod in mon. box
 Blaze & 40d nail in E side 44" Oak N 45° E 33.55'*
 Blaze & 40d nail in E side 12" Ash S 15° E 35.32'
 Blaze & 40d nail in SW side 10" Ash S 40° E 27.23'
 Blaze & 40d nail in S side 18" Oak S 75° E 32.75'
 Blaze & 40d nail in NW side PP S 60° W 95.75'
 PK W side 44" Oak N 45° E 32.81'* (same tree)
 PK W side 44" Oak S 10° W 90.07'
 C/L bit. W 11'±
 Meas. by hand



Signed by John C. Bueche Date 1-27-93

Surveyor's Michigan License No. 13027