

1993

COMMISSION

**Barry County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

MAY 14 11 08 AM '93

Sandy Schondelmaier
REGISTER OF DEEDS

002004

Register of Deeds Stamp & File Number

For corners in

<u>Barry</u> <small>(County)</small>	Located In:	Corner Code =#
1. Public Land Survey	T <u>2N</u> R <u>10W</u>	E-1 (NW, 4) Orangeville Twp.
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John C. Bueche in a field survey on January, 1993
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1 Information from Reynolds Nothing recorded
DNR 1976
1 1/2" iron pipe with 3/4" iron pipe
Inside w/plastic cap #12029
S 70° W 22.36' 20" B. Oak
S 25° W 44.38' 28" W. Oak
S 68° E 53.60' 9" B. Oak
West 48.35' SW cor. 33, 3-10

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1 Found iron with cap #12029
@ fence cor. South & West
As per above witnesses

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 3/4" iron with cap #12029
Blaze & 40d nail in S side 44" Oak S 80° W 73.85'
Blaze & 40d nail in S side 22" Oak S 70° W 22.67'
Blaze & 40d nail in E side 16" Oak S 20° W 62.78'
Blaze & 40d nail in W side 6" Ash N 50° W 52.27'
Blaze & 40d nail in S side 12" Oak N 85° E 19.30'
3/4" iron with cap #12029 SW cor. 33, 3-10 West 48.35'
Fence W is North 0.75'; fence South is East 0.60'
C/L road E-W is North 12'±
Meas: by hand



Signed by John C. Bueche Date 1-27-93
Surveyor's Michigan License No. 13027