

1993

Barry County Remonumentation

MAY 14 11 08 AM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Sandy Schondelmayer REGISTER OF DEEDS

For corners in

Barry

(County)

Located In:

Corner Code #

- 1. Public Land Survey 2N 10W E-5 (SE, 8) Orangeville Twp.
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

002005

Register of Deeds Stamp & File Number

I, John C. Bueche in a field survey on January 19 93 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A triangle marker is located at the intersection of column D and row 5.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-5 MDNR 1947 Found iron pipe & 2" x 2" stake @ intersection of fences Set 4" x 60" conc. post with brass plat 8" above ground No wit. given
LCRC #373, Sept., 1984 DNR conc. mon. with brass cap Nail in S side PP N 60° W 58.66' Nail in N side 14" Oak S 50° W 14.67' Nail in SW side 24" Oak S 30° E 42.91' E-W power line N 27'±

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5 Found MDNR mon. dated 1947 As per above wit. 14" Oak gone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5 MDNR mon. dated 1947 Set 40d nail over existing nail in S side PP (#124 on E side of pole) N 60° W 58.70' Blaze & 40d nail in SW side 24" Oak S 30° E 42.55' Blaze & 40d nail in E side 14" Oak S 10° W 32.70' Blaze & 40d nail in N side 8" Oak S 65° W 45.73' Blaze & 40d nail in E side 14" W. Cherry N 15° E 80.22' On old fence South; E-W power line N 27'± Meas. by hand

Signed by John C Bueche

Date 1-27-93

Surveyor's Michigan License No. 13027

