

SURVEY & REMONUMENTATION

1993

COMMISSION

**Barry County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

MAY 14 11 08 AM '93

Sandy Schindelmarer
REGISTER OF DEEDS

For corners in

<u>Barry</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>2N</u> R <u>10W</u>	E-6 (E 1/4, 17) Orangeville Twp.
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

002006

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	▲	16	15	14	13						
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John C. Bueche, in a field survey on January, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-6 MDNR 1947 **Nothing recorded**
 Found large pointed stone & bottom cor. fence post in line with fences N-S
 Set 4" x 60" conc. post with brass plate 8" above ground
 "V" notch in face 26" Elm N 60° W 14'
 "V" notch in face of the E tree of the 18" Twin W. Oak N 39° 45' E 44.5'
 "V" notch in face of the W tree of the 28" Twin W. Oak N 80° 45' E 46.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-6 Found MDNR mon. dated 1947
 Old "V" notch in face of the E tree of the 18" Twin Oak N 39° 45' E 44.5'±
 Old "V" notch in face of the W tree of the 28" Twin Oak N 80° 45' E 46.4'±

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-6 MDNR mon. dated 1947
 Blaze & 40d nail in W side 12" Oak N 50° E 40.70' (at base of nail)
 Blaze & 40d nail in S side 14" Oak N 85° E 67.32'
 Blaze & 40d nail in E side 12" Oak S 30° E 30.48'
 Blaze & 40d nail in E side 16" dbl. Oak S 15° W 42.37'
 Blaze & 40d nail in N side 10" Oak N 80° W 21.49'
 Blaze & 40d nail in E side 16" Oak N 15° W 52.48'
 C/L bit. rd. W 440'±, hse. on W side rd. #6522
 Meas. by hand



Signed by John C. Bueche Date 1-27-93
 Surveyor's Michigan License No. 13027