

**SURVEY & REMONUMENTATION**

1993

**COMMISSION**

**Barry County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

MAY 14 11 08 AM '93

Sandy Schondelmar  
REGISTER OF DEEDS

For corners in

<u>Barry</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>2N</u> R <u>10W</u>	E-8 (E 1/4, 20) Orangeville Twp.
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

**002008**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John C. Bueche in a field survey on January 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- |  |  |
|--|--|
| E-8 MDNR 1947  | LCRC #161 DNR mon.                             |
| Found 1 1/4" pipe, iron rod & stake in line with N fence | Nail W side 20" Tw. Cherry S 30° W 22.49'      |
| Set 4" x 60" conc. post with brass plate 8" above ground | Nail N side 16" Oak West 28.62'                |
| "V" notch in face 24" W. Oak S 40° 15' W 26.62'          | Nail W side 16" Tw. Oak N 15° E 36.43'         |
| "V" notch in face 10" W. Oak N 14° 30' E 36.36'          | 6" Cedar post w/public fishing sign S 45° E 1' |
| "V" notch in face 36" W. Oak S 75° E 64.45'              | C/L dirt trail N 13'±                          |

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- |  |                   |
|--|-------------------|
| E-8 Found MDNR mon. dated 1947 with 1 1/4" pipe on W side 1/2" rerod on E side | As per above wit. |
|--|-------------------|

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8 MDNR mon. dated 1947  
Blaze & 40d nail in SE side 10" Oak S 25° E 41.00'  
Blaze & 40d nail in N side 6" Maple S 70° E 37.73'  
Blaze & 40d nail in N side 22" Oak West 28.70'  
Blaze & 40d nail in NW side 22" Tw. Oak N 15° E 36.43'  
Blaze & 40d nail in S side 10" Oak N 30° W 34.22'  
Existing nail in W side Tw. 20" W. Cherry S 30° W 22.49'  
C/L dirt trail N 13'±  
Meas. by hand



Signed by John C Bueche Date 1-27-93  
Surveyor's Michigan License No. 13027