

**SURVEY &
REMONUMENTATION**

1993

COMMISSION

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

Barry County Remonumentation

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

May 14 11 08 AM '93

Sandy Schondelmayer

REGISTER OF DEEDS

002009

Register of Deeds Stamp & File Number

For corners in

Barry

(County)

Located in:

Corner Code #

- | | | | | | |
|------------------------------------|---|----|---|-----|------------------|
| 1. Public Land Survey | T | 2N | R | 10W | E-9 (SE, 20) |
| | T | | R | | Orangeville Twp. |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | R |
| | S | | T | | R |
| 3. Miscellaneous Property in Sec. | S | | T | | R |
| | S | | T | | R |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John C. Bueche, in a field survey on January, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-9 MDNR 1947
Found stone @ intersection of fences
Set 4" x 60" conc. post with brass plate
No wit. given

LCRC #160, July, 1975
MDNR mon.
14" Oak (blazed face) S 75° W 1.4'
8" Oak (blazed face) N 10° E 14'
8" Maple (blazed face) S 60° E 34.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9 Found MDNR mon. dated 1947
Old blaze on E side N 15° E 14'± face 3 old blazes
Old blaze on N side N 80° W 1.4'±
Old blaze on S side S 70° E 34.8'± face 3 old blazes

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9 MDNR mon. dated 1947
Blaze & 40d nail in E side 10" Oak N 15° E 14.65' (5' high)
Blaze & 40d nail in N side 14" Oak N 80° W 1.93'
Blaze & 40d nail in S side 12" Oak S 70° E 35.14'
Blaze & 40d nail in E side 10" Oak S 45° W 17.57'
Blaze & 40d nail in S side 10" Maple N 55° W 31.50' (5' high)
Blaze & 40d nail in SE side 12" Oak N 60° E 16.79'
2 track to tower S 200'±
Meas. by hand

Signed by John C Bueche

Date 1-27-93

Surveyor's Michigan License No. 13027

