

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 2 04 PM '93

Sandy Schondelmar
REGISTER OF DEEDS

Barry County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Barry

(County)

Located In:

Corner Code #

1. Public Land Survey

T 2N R 10W

G-3 (SE, 4)

T R

Orangeville Twp.

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No.

Recorded Plat

5. Private Claims

002099

Register of Deeds Stamp & File Number

I, John C. Bueche in a field survey on March 19 93
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-3 4" x 30" conc. Mon. MDNR
(Reynolds)
South 98.35' 12" B. Cherry
S 45° W 18.88' 18" C. Oak
West 16.15' 14" B. Oak

LCRC #404 Jan., 1990
Conc. Mon. @ fence cor. N-S & W
Nail SW side 24" Oak S 40° W 19.02'
Nail N side 24" Oak S 90° W 16.22'
Nail E side 16" Oak N 0° E 29.51'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-3 Found conc. Mon. without cap Same per above wit.
@ fence cor. N-S & W
4-10" W. Cherry S 0° E 98'±
Existing 40d nail in SE side 24" Oak S 45° W 19.03'
Existing 40d nail in N side 18"-24" Oak N 90° W 16.15'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3 Conc. Mon. without cap @ fence cor. N-S & W
Conc. nail & B.C. Remon. Tag in E side 4-10" W. Cherry S 0° E 98.01'
Existing 40d nail in SE side 24" Oak S 45° W 19.03'
Existing 40d nail in N side 18"-24" Oak N 90° W 16.15'
Existing 40d nail in E side 22" Oak N 0° E 29.50'
Conc. nail & B.C. Remon. Tag N side 8" Sasaffas N 85° E 19.34'
Conc. nail & B.C. Remon. Tag SW side 8" Oak S 35° E 29.34'
Meas. by hand

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION

Signed by John C. Bueche

Date Oct. 29, 1993

Surveyor's Michigan License No. 13027

