

1993

COMMISSION

Barry County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

MAY 14 11 08 AM '93

Sandy Schondelmayer  
REGISTER OF DEEDS

For corners in

<u>Barry County</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>10W</u>	G-6 (E 1/4, 16) Orangeville Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

002012

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on January, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-6 MDNR 1947  
Found stone  
No wit. given  
Nothing recorded

Reynolds  
Survey by Snell 1986  
Inform. Rogers  
Conc. mon.  
24" Aspen S 45° E 27.0'  
24" Maple N 45° E 48.3'  
Fence cor. S 10° E 43.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6 Found broken conc. mon. As per above wit.  
with bent 1/2" rerod

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6 Conc. mon. with bent 1/2" rerod  
Blaze & 40d nail in E side 14" Maple N 20° W 55.43'  
Blaze & 40d nail in W side 10" Elm S 30° W 44.15'  
Cap #31602 & nail in N side 18" Poplar N 75° W 43.00'  
Cap #31602 & nail in NW side 36" Maple N 30° E 47.60'  
Cap #31602 & nail in SW side 34" Aspen S 40° E 26.79'  
On C/L gravel road N; C/L gravel road W, South 25'±  
Meas. by hand



Signed by John C. Bueche Date 1-27-93

Surveyor's Michigan License No. 13027