

SURVEY & REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

1993

Barry County Remonumentation

MAY 14 11 08 AM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Sandy Schondelmarper  
REGISTER OF DEEDS

For corners in

<u>Barry County</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>10W</u>	G-7 (SE, 16) Orangeville Twp.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

002013

Register of Deeds Stamp & File Number

I, John C. Bueche in a field survey on January, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-7 MDNR 1947  
Found of stone @ intersection  
of fences  
Set 4" x 60" conc. post with brass plate  
12" above ground  
No wit. given

Nothing recorded

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7 Found MDNR mon. dated 1947  
On fence running N; old fence E; old fence in 24" Oak W;  
old fence down S  
Standing fence South, West 25'±

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7 MDNR mon. dated 1947  
Blaze & 40d nail in N side 12" Catalpa N 45° W 38.21'  
Blaze & 40d nail in N side 12" Ash S 85° W 25.68'  
Blaze & 40d nail in SE side 14" Oak S 50° W 30.45'  
Blaze & 40d nail in NE side 14" Oak S 20° E 39.93'  
Blaze & 40d nail in S side 8" Oak N 90° E 17.95'  
Blaze & 40d nail in E side dbl. 18" Oak N 00° E 65.79'  
Meas. by hand



Signed by John C Bueche Date 1-27-93

Surveyor's Michigan License No. 13027