

**SURVEY &  
REMONUMENTATION**

1993

**COMMISSION**

**Barry County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

MAY 14 11 08 AM '93

Sandy Schondelmayer  
REGISTER OF DEEDS

**002015**

Register of Deeds Stamp & File Number

For corners in

Barry

(County)

Located In:

Corner Code #

- |                                       |   |    |   |     |                  |
|---------------------------------------|---|----|---|-----|------------------|
| 1. Public Land Survey                 | T | 2N | R | 10W | G-9 (SE, 21)     |
|                                       | T |    | R |     | Orangeville Twp. |
|                                       | T |    | R |     |                  |
|                                       | T |    | R |     |                  |
| 2. Property Controlling in Section    | S |    | T | R   |                  |
|                                       | S |    | T | R   |                  |
| 3. Miscellaneous Property in Sec.     | S |    | T | R   |                  |
|                                       | S |    | T | R   |                  |
| 4. Lot No. _____, Recorded Plat _____ |   |    |   |     |                  |
| 5. Private Claims _____               |   |    |   |     |                  |

I, John C. Bueche, in a field survey on January, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-9 MDNR 1947 Nothing recorded  
Set 4" x 60" conc. post with brass  
Plate and post 6" x 7' @ intersection  
of fences  
No wit. given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9 Found MDNR mon. dated 1947  
Line of fence post North  
Old fence S, W, E

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9 MDNR mon. dated 1947  
Blaze & 40d nail in N side 16" Oak West 9.60'  
Blaze & 40d nail in E side 8" Oak N 25° W 23.18'  
Blaze & 40d nail in S side 14" Oak N 80° E 14.00'  
Blaze & 40d nail in SW side 14" Oak S 55° E 33.40'  
Blaze & 40d nail in N side 12" Oak S 45° W 24.81'  
Blaze & 40d nail in W side 16" Oak S 10° W 41.40'  
Meas. by hand



Signed by John C Bueche

Date 1-27-93

Surveyor's Michigan License No. 13027