

SURVEY & REMONUMENTATION

AUG 31 1994

COMMISSION

For corners in BARRY
(County)

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Located In: _____ Corner Code # _____

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

JUL 8 12 42 PM '94

Sandy Schindelmarper
REGISTER OF DEEDS

1. Public Land Survey

T 2N R 10W J-7
ORANGEVILLE TWP. SEC. 14 & 23

2. Property Controlling in Section

T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

002197

Register of Deeds Stamp & File Number

BRIAN REYNOLDS

03 APR

94

I, BRIAN REYNOLDS, in a field survey on 03 APR, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- G.L.O.: SYLVESTER SIBLEY D.S. 1827 (R10W, Pg.93): WEST CORRECTED 39.87ch.
A W. OAK - 18 - N29E - 17lnks.; A B. OAK - 30 - S32W - 57lnks.
 - A.C. WILLSON 1867 (L.2, Pg. 147): W. OAK - 15 - N52W - 39lnks.
 - COBB 01/APR/1890 (BOOK IX, Pg.93): FOUND U.S. BEARING
W. OAK - 18 - N29E - 17 - GREEN; SET STONE 21x12x8 & BRICK.
 - JAMES L. KING 09/APR/1974 (L.C.R.C. #163): SET 1/2" IRON IN FENCE CORNER.
CHECKED GOOD WITH OCCUPATION LINES WITHIN SECTION.
12" TWIN HICKORY - S45W - 24.12', 6" HICKORY - S70E - 20.19'
5" TWIN HICKORY - N20E - 18.97'
 - JAMES L. KING 11/APR/1974 (L.C.R.C. #132): SAME AS L.C.R.C. #163



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- LOOKED FOR 1/2" IRON AS STATED IN L.C.R.C.'S #132 & #163. FOUND NOTHING. DUG AROUND BASE OF 6" WOODEN FENCE CORNER TO FIND A SPIKE WITH PINK RIBBON. FURTHER EXCAVATION UNCOVERED BITS OF BRICK IN THE DIRECT AREA OF THE SPIKE. DETERMINED THAT BRICK FOUND WAS THAT OF COBB (1890). NO STONE RECOVERED. TOOK SPIKE OVER BRICK AT INTERSECTION OF N. - S. - E. - W. FENCES AS BEST EVIDENCE OF THE PERPETUATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET BARRY Co. REMONUMENTATION MONUMENT REPLACING SPIKE OVER BRICK:
- AT INTERSECTION OF N. - S. - E. - W. FENCES.
- CENTER OF 6" DIA. FENCE CORNER - S45W - +/- 1.2'
- FOUND NAIL & TAG - SW. FACE - 6" HICKORY - S60W - 20.17'
- N&T - E. FACE - 12" HICKORY - S10W - 3.75'
- N&T - S. FACE - 32" TWIN OAK - S85E - 34.29'
- N&T - N. FACE - 14" OAK - S60W - 19.59'
- N&T - W. FACE - 16" OAK - N50E - 14.33'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
MAY 3, 1994 BR
BRIAN REYNOLDS COUNTY SURVEYOR

Signed by [Signature]

Date JUNE 20, 1994

Surveyor's Michigan License No. 31602