

SURVEY & REMONUMENTATION

FEB 17 1998

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION



2628
Page: 1 of 1
12/16/1997 12:15P

For Corners in
BARRY COUNTY

Located In: Co)

Sandy Schondelmayer - Barry Co. LCRGR

Register of Deeds Stamp & File Number

1. Public Land Survey T..2N R..10WM-11..
SEC COR COMMON T..... R.....
TO SEC'S 25 & 36 T..... R.....
ORANGEVILLE TWP. T..... R.....

2. Property Controlling S.....T..... R.....
in Section S.....T..... R.....

3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....

4. Lot No....., Recorded Plat.....

5. Private Claims.....

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **RAYMOND MOORED**, in a field survey on **MAY, 1994** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO: JOHN MULLETT D.S. 1826 (R10W, P.67) Y. OAK 18 n431/2w 77; W OAK 7 S32W 03.
COUNTY SURVEYOR RECORDS: BOWEN 1876 (L.1,P.163) FOUND REMAINS OF OLD BEARINGS HICK 5 S85 1/2 W 49 MAPLE 5 N43 1/2 E 55; SET STONE, IRON & CROCKERY FOR CORNER.
BATEMAN 3, 4 AUGUST 1900 (L.1, P.352) & (L.3,P.38) HICKORY S 85 1/2 W. 49 LINKS
COBB NOV 11, 1912 HOPE TWP. BROWN F.B, P.15 BEYOND GLO TRANS.) SET LONG STAKE IN PIT OF STONE & BRK & EN. HICK 6 N 80°E 66 LKS, SUGAR 16 N 14 3/4 E 115 LKS.
COUNTY ROAD COMMISSION: 1965 IRON FOR CORNER
14"OAK E. 19.0'; 14" OAK 575' W 37.5'; 14" OAK S 35°E 36.15'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" IRON IN MON. BOX NEAR OCCUPATION LINE TO EAST. 14" OAK EAST 19.0' REMAINED.
MAPLE WITNESS TO NE BY COBB REMAINS.
SET BARRY COUNTY REMONUMENTATION IRON WITH CAP IN MON. BOX.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON 10 April, '95 *TR*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN MON. BOX
-NAIL IN S SIDE 18" OAK EAST 19.22'
-NAIL IN SW SIDE 40" MAPLE N15E 74.10'
-NAIL IN NW SIDE 33" OAK S45W 46.00'
-NAIL IN SW SIDE 30" OAK S45E 39.80'
-NAIL IN NE SIDE 24" OAK N30W 61.65'

Raymond Moored Date 12/11/97

Surveyor's Michigan License No. 26463

