

**SURVEY & REMONUMENTATION**

JUL 24 1997

COMMISSION

**BARRY COUNTY REMONUMENTATION**

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECORDS

MAR 5 9 25 AM '97

Sams...  
REGISTER OF DEEDS

002472

Register of Deeds Stamp & File Number

For corners in  
**BARRY**

(County)

Located In:

Corner Code #

- |                                       |   |           |   |           |             |
|---------------------------------------|---|-----------|---|-----------|-------------|
| 1. Public Land Survey                 | T | <u>3N</u> | R | <u>7W</u> | <u>B-10</u> |
| <b>CENTER OF SECTION 30</b>           | T | _____     | R | _____     | _____       |
| <b>CASTLETON TOWNSHIP</b>             | T | _____     | R | _____     | _____       |
|                                       | T | _____     | R | _____     | _____       |
| 2. Property Controlling               | S | _____     | T | _____     | _____       |
| in Section                            | S | _____     | T | _____     | _____       |
| 3. Miscellaneous                      | S | _____     | T | _____     | _____       |
| Property in Sec.                      | S | _____     | T | _____     | _____       |
| 4. Lot No. _____, Recorded Plat _____ |   |           |   |           |             |
| 5. Private Claims _____               |   |           |   |           |             |

**BRIAN REYNOLDS**

**7 NOVEMBER**

**96**

I, Brian Reynolds, in a field survey on 7 NOVEMBER, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	●	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. THIS CORNER NOT SET BY THE GENERAL LAND OFFICE.
2. NO REFERENCE FOUND IN THE COUNTY SURVEYOR RECORDS.
3. PLAT OF HOWARD POINT, BY CARL V. PERRY, (L.3, P.74) 7 AUG, 1951, REFERENCED NO WITNESSES
4. ACT 132 SURVEY BY JAMES L. KING, P.S. #14788, DEC., 1977 (L. 1, P. 468) "1/2" RE-ROD" 6.5' WEST OF EAST EDGE OF GRAVEL ROAD 14" HICKORY S40°W 34.22'
5. UNRECORDED SURVEY BY KEN BRANDT, P.S. #24587, PART OF THE NORTHEAST 1/4 OF SECTION 30, T3N R7W, CORNER WAS RE-ESTABLISHED FROM THE SURVEY BY KING, ITEM 4 ABOVE. IRON AND WITNESSES WERE REMOVED BY ROAD CONSTRUCTION c. 1985.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON BY BRANDT (#5 ABOVE). CONFIRMED POSITION WITH TIES TO SURVEY BY KING (ITEM #4 ABOVE). ACCEPTED POSITION AS MONUMENTED BY BRANDT AS PROPER RESTORATION OF CORNER POSITION. REPLACED FOUND IRON WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AND ALUMINUM CAP.

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
18 NOV. 96  
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (WITH ALUMINUM CAP)
- SET 20d NAIL W/REMON TAG IN THE NORTH SIDE OF A 24" ELM S78°E 109.98'
- SET 20d NAIL W/REMON TAG IN THE SOUTH SIDE OF A 15" ELM S70°E 65.63'
- NORTHEAST CORNER CONCRETE HOUSE FOUNDATION S21°W 297.46'
- NORTHWEST CORNER CONCRETE HOUSE FOUNDATION S25°W 307.08'
- 1/2" CAPPED IRON "REYNOLDS 31602" N33°E 24.22'
- CORNER LIES 3'+/- EAST OF CENTERLINE 13'+/- NORTH OF FENCE LINE EAST



Signed by

*Brian Reynolds*

Date

FEB 18, 1997

Surveyor's Michigan License No.

31602