

BARRY COUNTY REMONUMENTATION

JUL 24 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

STATE OF MICHIGAN
BARRY COUNTY
RECORDED

17 JUN 97 12:19 P.M.

SANDY SCHONDELMAYER
REGISTER OF DEEDS

002499

Register of Deeds Stamp & File Number

For Corners in BARRY Located In: _____ Corner Code # _____
(county)

1. Public Land Survey T 3N R 7W _____ E-11
CORNER COMMON TO T _____ R _____
SECTIONS 28, 29, 32, 33 T _____ R _____
CASTLETON TOWNSHIP T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____

5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|---|----|---|----|---|----|---|----|---|
| 2 | 6 | | 5 | | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

I, **Brian Reynolds**, in a field survey on **6 AUGUST, 1996** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830 (R7W, P.108) A BEECH 10 S74E 20 Do. 8 N81W 29

*** NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF CORNER MONUMENTATION. ESTABLISHED CORNER POSITION AT POINT THAT BEST HARMONIZES 1/4 LINE AND 1/8 LINE OCCUPATION WEST, NORTH, AND EAST.

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (WITH ALUMINUM CAP)

SET 20d NAIL W/REMON TAG IN THE NORTH SIDE OF A 10" MAPLE N83°W 146.84'

SET 20d NAIL W/REMON TAG IN THE NORTH SIDE OF A 10" MAPLE S83°W 187.08'

SET "PK" W/REMON TAG IN THE SOUTHEAST SIDE OF A UTILITY POLE N35°E 54.96'

SET "PK" W/REMON TAG IN THE NORTHEAST SIDE OF A UTILITY POLE N38°W 59.87'

SET "PK" W/REMON TAG IN THE EAST SIDE OF A UTILITY POLE S7°W 266.57'

CENTERLINE OF NORTH-SOUTH BITUMINOUS ROADWAY LIES WEST 5'+/-

ROUGHLY ON CENTERLINE OF GRAVEL ROAD WEST

CENTERLINE OF GRAVEL ROAD EAST LIES NORTH 8'+/-

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

3-11-'96

BR

BRIAN REYNOLDS

COUNTY SURVEYOR



Signed by

Brian Reynolds

Surveyor's Michigan License No

31602

Date

MAY 16, 1997