

STATE OF MICHIGAN
 COUNTY OF BARRY
 RECEIVED FOR RECORD

DEC 7 3 41 PM '93

Sandy Schindelmarer
 REGISTER OF DEEDS

002116

Register of Deeds Stamp & File Number

BARRY COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BARRY COUNTY

(County)

CASTLETON TOWNSHIP

1. Public Land Survey

Located In:

Corner Code #

T 3N R 7W

E-12

T R

T R

T R

T R

S T R

S T R

S T R

S T R

2. Property Controlling
 in Section

3. Miscellaneous
 Property in Sec.

4. Lot No.

Recorded Plat

5. Private Claims

I, ROBERT R. CARR, in a field survey on OCTOBER 14, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-12 G.L.O. SUGAR MAPLE 8" N70°E 18 LKS.
- G.L.O. SUGAR MAPLE 12" N66°W 29 LKS.
- COUNTY ROAD COMMISSION MONUMENT BOX.
- M-DOT RIGHT-OF-WAY MAP FOR M-79 SHOWS NO REFERENCE TO CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-12 FOUND BOAT SPIKE IN MONUMENT BOX ON CENTERLINE OF M-79 AND IN LINE WITH CENTERLINE OF N/S ROAD. ACCEPTED BOAT SPIKE AS REASONABLE PERPETUATION OF CORNER. REPLACED BOAT SPIKE WITH STANDARD BARRY COUNTY REMON STAKE AND CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-12 BARRY COUNTY REMON 3/4" STEEL ROD AND ALUMINUM CAP WITH CENTER PUNCH.
- NAIL AND SPOTTER IN WEST SIDE U-POLE S23°W 236.54 FEET.
- NAIL AND SPOTTER IN NORTH SIDE U-POLE S79°W 234.95 FEET.
- SW CORNER BARN FOUNDATION N34°E 188.73 FEET.
- NAIL AND SPOTTER IN SOUTH SIDE 16" ELM N83°E 287.90 FEET.

SURVEY &
 REMONUMENTATION

APR 05 1994

COMMISSION



Signed by

Robert R. Carr

Date NOV 10, 1993

Surveyor's Michigan License No.

20704