

MAY 20 1997

BARRY COUNTY REMONUMENTATION

DEC 9 2 09 PM '96

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Sandy Schindlmarer

REGISTER OF DEEDS

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code #
1. Public Land Survey CASTLETON TWP. 1/4 COR COMMON TO SEC'S 1	T <u>3</u> R <u>7W</u>	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

002428

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, RAYMOND MOORED, in a field survey on Sept, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. SYLVESTER SIBLEY D.S. 1830 (R7W, P.108) A. BEECH 6 S. 71 1/2 E. 48 A. SUGAR 14 S. 32W. 28. COUNTY SURVEYOR RECORDS SET STONE FOR CORNER A.D. RORK JUNE 20, 1866 (L.2, P.105)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF CORNER LOCATION. ESTABLISHED CORNER ON LINE BETWEEN SOUTHEAST AND SOUTH 1/4 CORNERS (G-13 & F-13, T4N, R7W) AT GLO JOG DISTANCE FROM G-13. ACCEPTED AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION. SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP.

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

13 Nov. '95  
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN MON BOX.
- NAIL & TAG IN NW SIDE 16" MAPLE N40°E 80.42'
- NAIL & TAG IN NW SIDE 20" MAPLE N35°E 131.40'
- NAIL & TAG IN NE SIDE POWER POLE N40°W 87.08'
- TOP CENTERLINE OF CABLE BOX S50°W 44.82'
- TOP CENTERLINE OF CABLE BOX S55°E 54.40'
- SE CORNER SEC 33 (G-13) EAST 29.70'
- IN CENTERLINE ROAD



Signed by Raymond Moored  
Surveyor's Michigan License No. 26463

Date 11/4/96