

BARRY COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Dec 7 3 41 PM '93

Sandy Schondelmayer
 REGISTER OF DEEDS

002117

Register of Deeds Stamp & File Number

For corners in

BARRY COUNTY (County)	Located In:	Corner Code #
CASTLETON TOWNSHIP	T 3 N R 7 W	G-7
1. Public Land Survey	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, ROBERT R. CARR, in a field survey on OCTOBER 14, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G-7 G.L.O WHITE OAK 6" S22-1/2°W 70 LKS.
 WHITE OAK 6" N52°W 44 LKS.
- COUNTY SURVEYOR F.J. MERSHON, LIBER 2, PG 218 BLACK; ASH 19" N44-1/2°E 12-1/2 LKS.
- BARRY COUNTY ROAD COMMISSION S45°W 58.51 FT. SPIKE IN POWER POLE NO. 360.
 S50°E 31.20 FT. SPIKE 24" TWIN ELM.
 N40°E 44.65 FT. SPIKE 18" TRIPLE ELM.
 S15°E 168.50 FT. SPIKE 30" ELM.
- L.C.R.C. NO. 136 5/8" IRON U-POLE N50°W 48.06 FT.
 U-POLE S50°W 47.53 FT.
- PIKE, 1973, IRON; U-POLE N50°W 48.06 FT.; U-POLE S50°W 47.53 FT.
 5 FEET EAST OF N/S ROAD CENTERLINE; 5 FEET SOUTH OF CENTERLINE E/W ROAD.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-7 FOUND 1/2" IRON PER CENTERLINE TIES BY PIKE, 1973.
 NO OTHER WITNESSES REMAINING.

SURVEY &
 REMONUMENTATION

APR 0 5 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-7 REPLACED 1/2" IRON WITH STANDARD BARRY COUNTY REMON: 3/4" STEEL ROD AND ALUMINUM CAP WITH CENTER PUNCH,
 5.8 FT EAST OF CENTERLINE OF ROAD TO SOUTH.
 4.4 FEET SOUTH OF CENTERLINE OF E/W ROAD.
 SOUTH END OF C.M.P. CULVERT S46°E 35.83 FEET.
 NE CORNER HOUSE FOUNDATION S40°W 195.87 FEET.
 NORTH END OF C.M.P. CULVERT N45°E 35.92 FEET.
 NAIL AND SPOTTER IN SOUTH SIDE 16" MAPLE S85°W 35.92 FT.



Signed by Robert R. Carr
 Surveyor's Michigan License No. 20704

Date Nov 10, 1993