

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 3 41 PM '93

Sandy Schondelmarer
REGISTER OF DEEDS

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BARRY COUNTY

(County)

CASTLETON TOWNSHIP

1. Public Land Survey

Located In:

Corner Code #

T 3 N R 7 W

G-12

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

002115

I, ROBERT R. CARR, in a field survey on OCTOBER 14, 19 93,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-12 G.L.O. BEECH 7" S29°E 39 LKS.
G.L.O. WHITE ASH 6" N34°W 18 LKS.
BOWEN, NOVEMBER 1875, FOUND STAKE, STONE & CROCKERY.
BARRY COUNTY ROAD COMMISSION MONUMENT BOX.
M-DOT M-79 RIGHT-OF-WAY MAP SHOW NO. REFERENCE TO CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12 FOUND BOAT SPIKE IN MONUMENT BOX 9.2 FEET SOUTH OF CENTERLINE OF M-79 AND IN LINE
WITH CENTERLINE OF ROAD TO SOUTH.
FINDING NO OTHER PERPETUATION OF CORNER, ACCEPTED BOAT SPIKE AS MOST REASONABLE
LOCATION OF CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 REPLACED BOAT SPIKE WITH STANDARD BARRY COUNTY REMON 3/4" STEEL ROD AND ALUMINUM CAP WITH
CENTER PUNCH.
NAIL AND SPOTTER IN WEST SIDE OF U-POLE S11°E 165.71 FEET.
NAIL AND SPOTTER IN NORTH SIDE OF U-POLE N66-1/2°W 222.18 FEET.
NAIL AND SPOTTER IN NORTH SIDE OF U-POLE S80°W 190.58 FEET.
FACE OF M-DOT RIGHT-OF-WAY MARKER N5°E 69.91 FEET
CENTERLINE M-79 NORTH 9.2 FEET.

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION



Signed by

ROBERT R. CARR

Surveyor's Michigan License No. 20704

Date Nov. 10, 1993