

**SURVEY &
REMONUMENTATION**

NOV 04 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
REGISTERED DEEDS

OCT 9 1995

Sandy S. Reynolds
REGISTERED DEEDS

002406

Register of Deeds Stamp & File Number

For corners in
BARRY

	(County)	Located In:		Corner Code #
		3N	7W	
CASTLETON TOWNSHIP				
1. Public Land Survey		T _____	R _____	G-13
		T _____	R _____	
		T _____	R _____	
		T _____	R _____	
2. Property Controlling in Section	S _____	T _____	R _____	
	S _____	T _____	R _____	
3. Miscellaneous Property in Sec.	S _____	T _____	R _____	
	S _____	T _____	R _____	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

DAVID L. CLIFFORD, in a field survey on **SEPTEMBER 24**, 19**96**

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. POST SET IN ORIGINAL GOVERNMENT SURVEY BY LUCIUS LYON, DEPUTY SURVEYOR IN DECEMBER 1825 AND TWO BEARING TREES RECORDED:
SUGAR 10" N68W 28 LKS (18.5')
SUGAR 7" N84E 25 LKS (16.5')
2. IN CASTLETON FIELD BOOK PAGE 64 BOWEN, COUNTY SURVEYOR SET STONE
3. I FIND NO FURTHER MENTION OF CORNER IN PUBLIC OR PRIVATE RECORDS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 1/2" BAR AT G-1, T2N, R7W, 2' WEST OF EAST EDGE SWIFT ON FENCE LINE TO WEST. EXCAVATED ENTIRE ROAD BED AND FOUND STONE 21.5' WEST OF FOUND IRON. TRAVERSE OF SOUTH LINE OF SECTION 33, T3N, R7W AND ALL OF SECTION 4, T2N, R7W SHOW STONE TO BE ALMOST EXACTLY THE DISTANCE FROM THE SOUTH 1/2 CORNER AS THE SOUTH 1/2 CORNER IS FROM THE SW CORNER OF SECTION 33. ACCEPTED STONE AS CORNER AS PERPETUATED BY BOWEN, COUNTY SURVEYOR. WE DRILLED HOLE IN STONE AND GROUTED 3/4" X 8" STEEL BAR WITH BARRY COUNTY REMONUMENTATION CAP INTO IT.

**ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON**

Oct 9, 1995 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 T3N R7W
3/4" DIAMETER X 8" STEEL BAR AND ALUMINUM CAP IMPRINTED "BARRY COUNTY REMONUMENTATION PS 31602 28409" IN STONE 2' WEST OF WEST EDGE SWIFT ROAD ON FENCE LINE TO WEST.
NAIL AND TAG 28409 IN NE SIDE OF 31" MAPLE, 35° NAZ., 42.17'
NAIL AND TAG 28409 IN NW SIDE OF 30" MAPLE, 29° NAZ., 71.39'
NAIL AND TAG 28409 IN NW SIDE OF 19" HACKBERRY, 41° NAZ., 49.75'
FACE OF R.R. RAIL FENCE POST, 273° NAZ., 23.73'
3/4" BAR & ALUMINUM CAP IMPRINTED PS 31602 28409(G-1 T2N R7W), 93° NAZ., 21.48'

Signed by *David Clifford*
25837

Date **OCTOBER 10, 1996**

Surveyor's Michigan License No. _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

