

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 3 41 PM '93

Sandy Schindelmarper
REGISTER OF DEEDS

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BARRY COUNTY
(County)
CASTLETON TOWNSHIP

Located In:

Corner Code #

1. Public Land Survey

T 3 N R 7 W

1-12

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number

000114

I, ROBERT R. CARR, in a field survey on OCTOBER 14, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1-12 G.L.O MAPLE 9" N78°E 22 LKS.
G.L.O. BLACK ASH 10" N46°W 30 LKS.
BOWEN, NOVEMBER, 1875, FOUND POST AND OLD BEARINGS.
BARRY COUNTY L.C.R.C. NO. 248 JOHN A. MERDZINSKI, P.S. NO. 10697, SET "T" IRON USING M-DOT CONSTRUCTION PLANS AND TIES TO CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1-12 FOUND "T" IRON AS PER L.C.R.C. NO. 248 AND ACCEPTED AS TRUE PERPETUATION OF CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-12 REPLACED "T" IRON WITH STANDARD BARRY COUNTY REMON 3/4" STEEL ROD AND ALUMINUM CAP WITH CENTER PUNCH.
NAIL AND SPOTTER IN EAST SIDE 10" ASH N16°E 17.14 FEET.
NAIL AND SPOTTER IN EAST SIDE 14" ASH N20°W 4.80 FEET.
NAIL AND SPOTTER IN NORTH SIDE TWIN 8" POPLAR N68°W 57.33 FEET.
3 FOOT EAST OF N/S FENCE LINE.
58.50 FEET NORTH OF ~~CENTERLINE~~ CENTERLINE OF OLD RAILROAD GRADE.

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION



Signed by Robert R. Carr
Surveyor's Michigan License No. 20704

Date NOV. 10, 1993