

MAY 20 1997

COMMISSION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY BARRY REC'D DEC 9 2 09 PM '96

For Corners in BARRY Located in: Corner Code #

1. Public Land Survey NORTH 1/4 COR. TO SEC. 2 CASTLETON TWP. T.3N R..7W ....J-1.....

2. Property Controlling in Section S.....T..... R..... S.....T..... R.....

3. Miscellaneous Property in Sec. S..... T..... R..... S..... T..... R.....

4. Lot No....., Recorded Plat..... 5. Private Claims.....

I, RAYMOND MOORED, in a field survey on 9 AUGUST, 1994 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: CORNER NOT SET BY GLO. NO HISTORICAL DATA AVAILABLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: FOUND NO EVIDENCE OF EXISTING CORNER. SET STANDARD BARRY CO. REMONUMENTATION IRON WITH CAP ON LINE BETWEEN K-1 AND H-1 OF CASTLETON ON 1/4 LINE OCCUPATION LINE TO SOUTH. POSITION FITS 1/8 LINE OCCUPATION 1/4 MILE EAST IN NE 1/4 OF SECTION 2. ACCEPTED POSITION AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP -NAIL & TAG IN W'LY SIDE 15" MAPLE S2°E 29.24' -NAIL & TAG IN E SIDE 36" HICKORY N5°W 37.15' -C/L COATS GROVE ROAD NORTH 2.6' -NE COR SEC 2 (K-1) EAST 2662.82' - S1/4 COR SEC. 35, WOODLAND, EAST 67.87'

Sandy Schmidt-Sumayer REGISTER OF DEEDS

002422


Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column J and row 1.

Signed by Raymond Moored

Date 12/2/96

Surveyor's Michigan License No. 26463



ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON

13 Nov. 95 BRIAN REYNOLDS COUNTY SURVEYOR