

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 3 41 PM '93

Sandy Schondelmar
REGISTER OF DEEDS

002119

Register of Deeds Stamp & File Number

For corners in

BARRY COUNTY
(County)

CASTLETON TOWNSHIP

1. Public Land Survey

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

4. Lot No. _____; Recorded Plat _____

5. Private Claims _____

Located In:	Corner Code --#
T <u>3</u> N R <u>7</u> W	<u>K-11</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, ROBERT R. CARR, in a field survey on OCTOBER 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-11 G.L.O. BEECH 22" S76°E 18 LKS.
BEECH 15" N76°W 2 LKS.
LEE COBB, 1908 FOUND CORNER STONE & WITNESS TREES; BEECH 12" S55- 2.61-3/4 CHAINS.
BEECH 14" N86°E 53 LKS.
BARRY COUNTY ROAD COMMISSION PILE, 7/73; IRON ON CENTERLINE OF ROAD NORTH; U-POLE N55°W 54.13 FT.
16" PINE S55°E 39.70 FT.; 5.2 FT SOUTH OF CENTERLINE OF E/W ROAD
30" MAPLE N45°E 49.39 FT.
L.C.R.C. NO. 141 KING 9/04/73.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-11 FOUND 1/2" IRON OVER OLD 2-1/2" PIPE MATCHING ROAD COMMISSION AND L.C.R.C. NO. 141 WITNESSES TO U-POLE, 30" MAPLE AND 16" PINE.
ACCEPTED 2-1/2" PIPE AS TRUE PERPETUATION OF CORNER.

SURVEY &
REMONUMENTATION
APR 05 1994
COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11 REMOVED 1/2" IRON AND PLACED STANDARD BARRY COUNTY REMON 3/4" STEEL ROD AND ALUMINUM CAP WITH CENTER PUNCH OVER EXISTING 2-1/2" PIPE.
NAIL AND SPOTTER IN SE SIDE OF 30" MAPLE N50°E 49.11 FT.
NAIL AND SPOTTER IN NE SIDE OF U-POLE N57°W 54.32 FT.
NAIL AND SPOTTER IN W SIDE OF 18" PINE S44°E 39.56 FT.
NAIL AND SPOTTER IN W SIDE OF U-POLE S23°W 174.05 FT.
9 FOOT EAST OF CENTERLINE ROAD SOUTH; 0.5 FEET WEST OF CENTERLINE ROAD NORTH; 5 FOOT SOUTH OF CENTERLINE E/W ROAD.

Signed by Robert R. Carr
Surveyor's Michigan License No. 20704

Date Nov 10, 1993