

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 3 41 PM '93

Sandy Schindelmarper
REGISTER OF DEEDS

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BARRY COUNTY
(County)

Located in:

Corner Code #

CASTLETON TOWNSHIP

1. Public Land Survey

T 3 N R 7 W

K-12

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

000113

Register of Deeds Stamp & File Number

I, ROBERT R. CARR in a field survey on OCTOBER 15, 19 93
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-12 G.L.O. BEECH 22" N84°E 7 LKS.
BEECH 18" S83°W 37 LKS.
L.C.R.C. NO. 251 MERDZINSKI, P.S. NO. 10697.
M-DOT WITNESS CARD 11/15/90 BY SCHAUB.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12 MERDZINSKI, 1978, ON L.C.R.C. NO. 251 FOUND AND ACCEPTED 1/2" IRON IN CONCRETE PER ASSESSOR'S
PLAT NO. 1, VILLAGE OF NASHVILLE.
SCHAUB/M-DOT, 1990, FOUND 3/4" PIPE IN CONCRETE PER MERDZINSKI'S WITNESSES.
FOUND PIPE IN CONCRETE WITH BRICK AND CROCKERY AROUND MATCHING M-DOT WITNESSES TO
HOUSE AND 36" STUMP.

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 REPLACED PIPE IN CONCRETE WITH STANDARD BARRY COUNTY REMON 3/4" STEEL ROD AND ALUMINUM CAP
WITH CENTER PUNCH.
SW CORNER FRAME HOUSE FOUNDATION S51°E 76.63 FT.
SE CORNER BRICK HOUSE FOUNDATION N41°W 70.21 FT.
SW CORNER BLOCK BLDG N76°E 194.75 FT.
SE RIM OF MANHOLE N40°W 17.62 FT.
NAIL AND SPOTTER IN WEST SIDE OF 24" MAPLE S28°E 87.40 FT.



Signed by Robert R. Carr
Surveyor's Michigan License No. 20704

Date Nov 10, 1993