

1993

COMMISSION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF BARRY RECEIVED FOR RECORD

JUL 20 11 20 AM '93

Sandy Schondalmarer REGISTER OF DEEDS

002053

For corners in

Form with fields for County (BARRY), Located In, Corner Code (B-7), and survey details (Public Land Survey, Property Controlling, etc.)

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, BRIAN REYNOLDS, in a field survey on 22 MAY, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. : COBB: (PG. 111, BOOK IX) (NOV. 12, 1890)
W. OAK 14 S29W 36 W. FROM C-7 40.14CH.; FOUND STAKE & ONE GOV'T. BEARING;
" 7 N77E 11 W. OAK 7, N77E, 11.
SET STONE 18x10x4 & STAKE.

WILLIAMS & WORKS PLAT OF COOK ADDITION (1965) 2236.22' TO A-7
WILLIAMS & WORKS SECTION BREAKDOWN (1975) 2239.3' TO A-7
PLAT OF LINCOLN PARK ADDITION "CITY MONUMENT" T.O. WILLIAMS (1905)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3" x 24" CLAY TILE WITH MOLDED "X" & HOLE ON TOP.
AFTER REMOVAL OF CLAY TILE FOR REMONUMENTATION, FOUND SECOND CLAY TILE DIRECTLY UNDERNEATH.
CLAY TILE TIED INTO BY "WILLIAMS & WORKS" IN SURVEY IN SEC. 18 & 19 OF HASTINGS TOWNSHIP.
MEASURED DISTANCE TO A-7 2237.85' (REYNOLD'S 22MAY93)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" IRON PIN W/ALUM. REMON. CAP & PUNCH HOLE OVER 3" x 24" CLAY TILE; STABILIZED WITH CONCRETE AND STONES.
(40 D NAIL W/BARRY Co. SHINER FOR WITNESS)
N. FACE - 10" OAK - S56E - 76.05'
N. FACE - 10" OAK - S46E - 71.16'
SE. FACE - 8" ASH - S40W - 46.72'
SE. FACE - 10" LOCUST - N62E - 98.40'
POWER LINE +/- 4' N.

Signed by [Signature] Date 7-13-93
Surveyor's Michigan License No. 31602