

OCT 27 1994

BARRY COUNTY REMONUMENTATION

OCT 7 2 04 PM '94

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BARRY

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 3N R 8W Corner Code # C-3
CORNER COMMON TO SECTIONS 5,6,7, AND 8 HASTINGS TOWNSHIP
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Sandy Schindelmarper

REGISTER OF DEEDS

002236

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, BRIAN REYNOLDS, in a field survey on 7 SEPTEMBER, 19 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1 GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830 (R8W,P.127) A. RED OAK 34 N46 1/2E 71 Do. 30 S74W 53
- 2 COUNTY SURVEYOR RECORDS: A.D. RORK, NOV. 21, 1866, (L.2, P.117) "FOUND BEARINGS" ALSO: CRESSEY, 17 APRIL, 1874 (L.1, P.60); W. OAK 20 S52 1/2W 145 RED OAK 8 S56 1/4W 71 ALSO: BOWEN, NOV. 23, 1878 (L.1, P.266); "FOUND STAKE AND OLD BEARINGS NEW ONES" BEECH 16 S16 1/2W 39 HICK 8 S86W 21
- 3 COUNTY ROAD COMMISSION: "1/2" IRON ROD, MONU. BOX IN PAV." 24" MAPLE E30S 31.30' 20" ELM S45W 28.58'
- 4 MICHIGAN DEPARTMENT OF TRANSPORTATION: (1948 HIGHWAY PLANS PAGE 5) "CROCKERY IN MON. BOX 1.45' L OF STA. 26+46.0"
- 5 LAND CORNER RECORDATION CERTIFICATE: #82 BY JAMES L. KING, P.S. #14766, NOV. 26 1972, "FOUND IRON STAKE IN MONUMENT BOX" IRON STAKE IN MON. BOX ON WEST SIDE OF CENTERLINE OF M-43 2645.63' NORTH OF E. 1/4 POST SECTION 7
- 6 SURVEY BY ROY F. DEHAVEN, P.S. #3380, 11 MARCH 1975 (ACT 132 SURVEY L.1, P.288-289) "MONUMENT BOX IN PAVEMENT" TIES 24" MAPLE S30E 31.3' 20" ELM S45W 28.6'
- 7 SURVEY BY ROY F. DEHAVEN, P.S. #3380, 23 SEPT., 1976 (ACT 132 SURVEY L.1, P.352) "IN MON. BOX SET IN PAVEMENT 1.45' WEST OF C/L PAV."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**FOUND 1" SOLID IRON IN MONUMENT BOX, 1 FOOT+ BELOW GRADE
 DUE TO DIFFICULTY REMOVING FOUND IRON, IT WAS LEFT IN PLACE.
 ACCEPTED FOUND IRON AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION.**

ACT 345 BARRY COUNTY REMONUMENTATION
 APPROVED BY PEER REVIEW AT A MEETING HELD ON

4 Oct '94
BRIAN REYNOLDS COUNTY SURVEYOR



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

WITNESSES TO FOUND 1" IRON IN MONUMENT BOX

- SOUTHEAST CORNER ONE STORY BRICK HOUSE N76W 89.73'
- NORTHEAST CORNER ONE STORY BRICK HOUSE N55W 105.04'
- SET PK NAIL AND REMON TAG IN SOUTHWEST SIDE OF A POWER POLE N27W 127.16'
- TOP OF HIGHEST POINT ON FIRE HYDRANT S88E 33.49'
- SET PK NAIL AND REMON TAG IN THE NORTH SIDE OF A POWER POLE S86E 55.13'
- FOUND NAIL IN THE SOUTHWEST SIDE OF A POWER POLE S20E 160.92'

Signed by [Signature]
 Surveyor's Michigan License No. 31602

Date OCT 2, 1994