

SURVEY & REMONUMENTATION

JUL 24 1997

COMMISSION

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in <u>BARRY</u> (county)	Located In:	Corner Code #
1. Public Land Survey SOUTH 1/4 CORNER SECTION 33 HASTINGS TOWNSHIP ON TOWNSHIP LINE	T <u>3N</u> R <u>8W</u> T _____ R _____ T _____ R _____ T _____ R _____	<u>F-13</u> _____ _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No _____, Recorded Plat _____		
5. Private Claims _____		

002510

STATE OF MICHIGAN
BARRY COUNTY
RECORDED

17 JUN 97 12:21 P.M.

SANDY SCHONDELMAYER

Register of Deeds Stamp & File Number

I, **Brian Reynolds**, in a field survey on **17 JULY, 1996** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: JOHN MULLETT, D.S. 1826 (R8W, P.93) W. OAK 9 N36E 25 Do. 9 N43W 20
- COUNTY SURVEYOR RECORDS: BOWEN, 1875 (L.1, P.126) "FOUND OLD BEARINGS, TOOK NEW ONES" SUG MAPLE 10 N67E 41
- ALSO: LEE S. COBB, DEC. 9, 1889 (BOOK IX, P.83) "FOUND POST & TREES"
- LAND CORNER RECORDATION CERTIFICATE: #86, BY JAMES L. KING, P.S. #14766, MARCH, 1973 "FOUND WELL POINT AT FENCE CORNER" "WELL POINT" IN EAST AND WEST FENCE IN LINE WITH FENCE NORTH CLUMP OF 10"-12" OAKS N70°W 30.68' 14" OAK N15°W 17.68'
- PRIVATE NOTES OF CARROL PIKE (c.1973) "WELL POINT IN EW FENCE" WITNESSES ARE THE SAME AS IN ITEM # 4 ABOVE.

*** NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND WELL POINT AT INTERSECTION OF NORTH, EAST, & WEST FENCES WITH ALL WITNESSES BY PIKE AND KING.
ACCEPTED FOUND WELL POINT AS BEST AVAILABLE EVIDENCE OF CORNER POSITION.
REPLACED FOUND WELL POINT WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
SET 20d NAIL W/REMON TAG IN THE EAST SIDE OF A 6" MAPLE N6°E 27.20'
FOUND NAIL IN THE SOUTH SIDE OF A 12" CLUSTER OF OAKS N70°W 30.66'
FOUND NAIL IN THE WEST SIDE OF A 16" OAK N15°W 17.72' DECAYING WOOD FENCE CORNER POST N00°E 0.20'
IN LINE WITH FENCES RUNNING NORTH-EAST-WEST F-1, T2N, R8W LIES EAST 24.09'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

5-13-'96 *BR*
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by *[Signature]*
Surveyor's Michigan License No. 31602

Date MAY 16, 1997