

**SURVEY & REMONUMENTATION**

FEB 17 1998

Barry County Remonumentation

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in SECTION  
Barry  
 (County)

Located In: Corner Code =#

1. Public Land Survey

T 3N R 8W I-7 (SW 14)  
 Hastings Twp.

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_



**2624**  
 Page: 1 of 2  
 10/20/1997 01:01P

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Steven Koerber August 31 1996

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- I-7 GLO - Sylvester Sibley D.S. 1830  
A. Beech 12
- 1. A.C. Willson 1867  
Found GLO Beech & took new bearings.  
W. Oak stump 4.5 S43W 73  
Do. 43 N43 1/2W 90
- 2. Cobb 1891  
fnd stone & put brick  
Apple 12 N18 1/2E 68 1/4 noched  
Lynn 3 S42 1/4E 60 3/4 blazed

Additional info. on back

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-7 Found 3/4" iron pipe  
Fnd. spike in 32" Maple S40W 60.0'  
Fnd. spike in 22" Pine N50W 35.60  
C/L 24" Pine stump N50E 43.0'  
And is accepted as a careful and faithful perpetuation of the position of the original corner.

ACT 345 BARRY COUNTY REMONUMENTATION  
 APPROVED BY PEER REVIEW AT A MEETING HELD ON  
JULY 8, 1994  
 BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-7 Replaced 3/4" iron pipe with Standard Barry Co. Mon. ( 3/4" x 24" Iron Rod with Aluminum cap)  
 Set spike & Barry Co. Remon. tag in W side Guy Pole S 28° W 49.42'  
 Set spike & Barry Co. Remon. tag in NW side 12" Walnut S 60° W 44.21'  
 Fnd. spike in E. side 24" Spruce N 40° W 35.51'  
 Capped rerod North 33.00'  
 C/L Center Road North 3.5'  
 C/L Mathison Road East 0'

Page 1 of 2

Signed by [Signature] Date 10-13-1997  
 Surveyor's Michigan License No. 39085



**SURVEY &  
REMONUMENTATION**

**FEB 17 1998**



**2624**

**Page: 2 of 2**  
10/20/1997 01:01P

Sandy Schondelmayer - Barry Co. LCRCR

**SECTION**

Page 2 of 2

3. no date  
Center Road plans F.B. P. 4, & Bound Road Comm. Surveys P. 69  
Pointed limestone  
Spike in 14" Maple S15W 60.0'  
Spike in 16" Maple S30W 59.15'  
Spike in 16" Pine N45E 43.35'
  
4. no date  
Pointed Limestone  
14" Maple S-SE 60.0'  
16" Maple S30W 59.15'  
16" Pine N45E 43.35'
  
5. Act 132 Survey L.1, P. 140, (10-23-1973)  
William Hume Rogers  
Iron over pointed limestone  
Spike in 24" Oak S30E  
Spike in E side 28" Maple S40W 60.0'  
Spike in 22" Pine N50E 43.0'  
Spike in N side 24" Pine N50E 43.0'