

1993

COMMISSION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF BARRY RECEIVED FOR RECORD

JUL 20 11 20 AM '93

Sandy Schondelmarer REGISTER OF DEEDS

For corners in

BARRY

(County)

Located In:

Corner Code #

1. Public Land Survey

3N 8W I-12

T R HASTINGS TWP

T R (1/4 COR. SEC. 34-35)

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. , Recorded Plat

5. Private Claims

002048

Register of Deeds Stamp & File Number

I, BRIAN REYNOLDS, in a field survey on MAY, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


Grid table with columns A-L and rows 1-13. A dot is marked at row 12, column J.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. : Set post W. Oak 8 N68E 5 " " 7 N88W 23

Bowen 1878 (L.1, P.216) 39.95 chains N of I-13; 40.13 chains S of I-11; U.S. bearings live; Set stone & stake

LCRC #89 (J. L. King, Mar 73) Set by proportional methods; 1" pipe; Clump of Cherrys S40E, 34.0' 8" triple walnuts N05W, 4.85' In line with N-S fence; E-W fence S. 7'



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

REYNOLDS (JAN 93)

Found "King's" 1" pipe lying flat on ground, cherry clump intact, walnuts gone. Dug around fence corner. Found circle of stones and crockery. Set 1" iron bar in center of stones.

SET 1" IRON BAR R-R TIE FC. COR. NW +/-1' W. FACE DOUBLE MAPLE S20E 27.78' N. FACE 10" OAK S85E 45.78' N. FACE 24" OAK N60E 24.34' NE. FACE 10" POPLAR N15W 22.30' FENCES N.-S.-W. (40 D NAILS WITH YELLOW CAPS FOR WIT.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ALL PREVIOUS WITNESSES AND 1" IRON BAR PRESENT AND CORRECT.

NEW WITNESSES:

40 D NAIL - BARRY Co. SHINER - E. FACE - 12" OAK - N05W - 14.69'

" " NW. FACE - NE. TRUNK - CLUMP 10" BLACK CHERRYS - S30W - 18.32'

Signed by

[Signature]

Date

7-13-93

Surveyor's Michigan License No.

31602