

FEB 17 1998

SECTION

Barry County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Barry

(County)	Located In:	Corner Code #
1. Public Land Survey	T 3N R 8W	J-6 (Center 14)
	T R	Hastings Twp.
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	



2622
Page: 1 of 1
10/20/1997 01:01P

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Steven Koerber August 31 96

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- J-6 Corner not set by GLO
- 1. Wilson 1867 Stone & brick Beech 14, N68 1/2W 64
- 2. Bowen Dec. 24, 1877 Set Stone & Brick at intersection of 1/4 lines Beech 14 N68 1/2W 64
- 3. Seth Pratt same wits as No. 2

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-6 Found bricks and crockery pieces as the monument representing the corner. Accepted found bricks and crockery as best evidence of historical position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-6 Set Standard Barry Co. Mon. (3/4" x 24" Iron Rod with Aluminum cap)
- Set spike & Barry Co. Remon. tag in N side 24" Maple S80W 24.31'
- Set spike & Barry Co. Remon. tag in S side 14" Ash N70°W 21.33'
- Set spike & Barry Co. Remon. tag in W side 18" Oak N5°W 37.96'
- Set spike & Barry Co. Remon tag in W side 8" Birch S25W 28.05'
- NE corner metal cattle shed N40E 81.7'
- Tree line to East 3' North

A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1						
3												
4	7	9	9	10	11	12						
5												
6	16	17	16	15	13							
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
JULY 8, 1996
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by Steven Koerber Date 10-13-1997
Surveyor's Michigan License No. 39085