

FEB 17 1998

Barry County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Barry

| (County) | Located In: | Corner Code # |
|------------------------------------|--------------------------------------------------------------------|---------------------------------|
| 1. Public Land Survey | T 3N R 8W T _____ R _____ T _____ R _____ T _____ R _____ | J-7 (S 1/4 14) Hastings Twp. |
| 2. Property Controlling in Section | S _____ T _____ R _____ S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ S _____ T _____ R _____ | |



2623

Page: 1 of 2
10/20/1997 01:01P

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

Steven Koerber August 31 1996

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------|
| J-7 GLO - Sylvester Sibley D.S. 1830 Beech 14 N74E 13 Beech 17 S11W 34 | 1. A.C. Willson 1867 Set post Butternut 5 S74W 70 Beech 12 S56 1/2E 68 1/2 | 2. Bowen 1877 Found B.Hillson's B.T. Set stake & Stone for corner Sugar 12 S19E 39 Sugar 12 S73W 109 |
|------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------|

Additional info. on back

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-7 Found 3/8" Bolt and excavated under the bolt position for the Iron and brick as indicated in the record. Found no record of iron and brick under the 3/8" bolt.
Found Reynolds capped rerod. Discussion with Brian Reynolds revealed that he set the rerod using Barry County Road Commission road alignment notes to reset the corner position using proportionate measurement and angular measurement deflection as indicated by the Road Commission notes for Center Road alignment.
Accepted the rerod and is accepted as a careful and faithful reestablishment of the position of the corner.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
SEPT 9, 1996
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | | |
|-----|-----------------------------------------------------------------------------------|------|--------|
| J-7 | Set Standard Barry Co. Mon. (3/4" x 24" Iron Rod with Aluminum cap) in mon. box. | | |
| | Set spike & Barry Co. Remon. tag in E side 8" Ash | N0E | 44.55' |
| | Fnd spike with Reynolds washer in E. side 8" Elm | N35E | 32.02' |
| | Set spike & Barry Co. Remon. tag in W side 18" Elm | S10E | 53.37' |
| | Fnd. Spike with Reynolds washer in E. side 14" Maple | S10W | 39.92' |
| | Capped N/A rerod South | | 33.10' |
| | C/L Center Road South | | 4.8' |
| | Bolt Spike East | | 10.85' |



Signed by Steven Koerber Date 10-13-1997
Surveyor's Michigan License No. 39085

**SURVEY &
REMONUMENTATION**

FEB 17 1998

SECTION



2623

Page: 2 of 2
10/20/1997 01:01P

Sandy Schendelmayer - Barry Co. LCRCR

Page 2 of 2

3. No date
Barry County Road Commission (Center Road Plans P.6)
Iron & Brick
Spike in 24" Cherry N50W 44.48'
Spike in 34" Maple S10E 33.37'
Spike in 24" Ash S1E 66.71'
4. No name or date
1/2" iron ref. Rod.
24" Wild Cherry N50W 44.48'
34" Maple S10E 33.37'
24" Ash S10E 66.71'
5. 10-23-1973
William Hume Rogers
Recorded survey L. 1, Pg. 140 (Barry County)
3/8" Bolt over iron and Brick
Wood Anchor fence post South 34.44'
Spike in N. side 14" Maple S47W 53.0'
Spike in S. side 14" Basswood S75E 94.0'
6. Reynolds Land Surveying notes
Set 1/2" iron with cap
Tele riser S50E 53.40'
Twin box elder S10E 53.40'
12" Maple S5W 39.90'
5" Elm N25E 32.10'
C/I Center Road South 4.8'