

**SURVEY & REMONUMENTATION**

Barry County Remonumentation

FEB 17 1998

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Barry

**SECTION**  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 3N R 8W

K-7 (SE 14)

T \_\_\_\_\_ R \_\_\_\_\_

Hastings Twp.

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_



**2626**

Page: 1 of 2  
10/20/1997 01:01P

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Steven Koerber August 31 96

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- K-7 GLO - Sylvester Sibley D.S. 1830
  - A. Beech 7 N63W 27
  - A. Sugar 11 S34E 38
- 1. A.C. Willson 1867
  - Brick & Stone
  - Beech 10 S46 1/2W 66 1/2
  - Beech 10 N9 1/2W 78
- 2. Bowen Dec 24 1877
  - Found stake, stone and bearings set by Willson.

Additional info. on back

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-7 Found Railroad Spike as indicated in No. 7 above.
    - Found spike in E side 14" Oak SW 101.90'
    - Found spike in North side 20" Maple WSW 98.88'
    - Found spike in P. Pole SE 82.92'
    - Found spike in E. side 15" Basswood NE 64.31'
- Accepted the Railroad spike and is accepted as a careful and faithful reestablishment of the position of the corner.

**ACT 345 BARRY COUNTY REMONUMENTATION**  
**APPROVED BY PEER REVIEW AT A MEETING HELD ON**  
JULY 8, 1996 BR  
**BRIAN REYNOLDS** COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-7 Set Standard Barry Co. Mon. ( 3/4" x 24" Iron Rod with Aluminum cap) in mon. box.
  - Set spike & Barry Co. Remon tag in E side 20" Oak S25W 101.82'
  - Set spike & Barry Co. Remon tag in S. side 20" Maple S75W 98.75'
  - Found spike in SE side P. Pole S35E 82.92'
  - Found spike in E. side 15" Basswood N25E 64.31'



Signed by [Signature] Date 10-13-1997  
Surveyor's Michigan License No. 39085

SURVEY &  
REMONUMENTATION

FEB 17 1998



2626

Page: 2 of 2  
10/20/1997 01:01P

Sandy Schondelmayer - Barry Co. LCRCR

Page 2 of 2

SECTION

3. May 9, 1892  
Cobb  
Found Willson's trees, set stone 24x10x6 and brick
  
4. Barry Co. Road Comm.  
(Center Road Plans, P.6 & bound road plans pg. 69)  
Pointed Rock  
Spike in 30" Beech S45W 43.40'  
Spike in 8" Bitter Hickory in fence S40E 48.35'  
Spike in 8" Black Oak N10E 66.91'
  
5. Various witness cards  
No date or name  
Pointed Rock  
Same wits as in No. 4
  
6. Act 132 survey L. 1, pg 140  
William Hume Rogers  
10-23-1973  
Spike over pointed stone  
Spike in W. side 22" Black Oak N10E 67.0'  
Fence corner N45E 45.0'  
Spike in SW side Tele Pole S45E 68.8'
  
7. L.C.R.C. 348  
March 18, 1983  
Carl P. Englert, Jr.  
Found nail, Set R.R. spike  
9" Oak SW 101.97'  
14" Maple WSW 98.88'  
P. Pole SE 83.00'  
15" Basswood NE 64.33'