

Barry County Remonumentation

SURVEY &  
REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

APR 04 2000

For corners in

Barry	Located In:	Corner Code #
(County)	3N 8W	L-6 (Center 1/4, 13)
1. Public Land Survey	T ___ R ___	Hastings Twp.
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SECTION



**2846**  
Page: 1 of  
12/07/1999 08:3

Darla K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Steven Koerber, in a field survey on April 8, 1988 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14			
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-6 Corner not set by GLO 1. November 2, 1878 Frank Bowen set a intersection of 1/4 lines Sugar 28, S49 1/2°E 12 1/2; Do. 22,N31°W 11

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-6 Found concrete rock pile with iron post centered in the pile. Pieces of brick were unearthed in the rocks stacked in the rock pile. Fence lines to the East-West and South from the center of the rock pile. Epoxy cemented a Barry County Remonumentation cap into the rock pile at the center of the iron post which was broken off at the top of the rock pile.

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

9 FEB 98 BR  
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-6 Epoxy cemented a Barry County Remonumentation cap into the rock pile at the center of the iron post which was broken off at the top of the rock pile.  
Set nail & BC Remon tag in S. side 10" Maple S70°W 7.35'  
Set nail & BC Remon tag in NW side 14" Ash S50°W 32.71'  
Set nail & BC Remon tag in W. side 12" Maple S0°W 26.24'  
Set nail & BC Remon tag in SW. side 10" Maple S45°E 30.28'  
Fence lines to the East-West and South from the center of the rock pile.

Signed by [Signature]  
Surveyor's Michigan License No. 39085

Date 11-22-1999

