

Barry County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY & REMONUMENTATION

APR 04 2000

SECTION

For corners in

Barry

(County)

Located In:

Corner Code #

1. Public Land Survey

3N 8W

L-7(South 1/4, 13)

Hastings Twp.

T ___ R ___
T ___ R ___
T ___ R ___
T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___
S ___ T ___ R ___

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

2847
Page: 1 of 1
12/07/1999 09:31

Darla K. Burghdoff - Barry Co. LRCR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Steven Koerber, in a field survey on April 8, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

L-7 GLO 1830 Sylvester Sibley DS West corrected between 13&24 40.22 set post on true line An' Aspin 7, N31 1/2°E 64, A Tamarak 6 S41 1/2°E 172
I. May 9, 1892 Lee Cobb Identified by stake and witnesses by "Pratt" 1885 Tam 6 S41 1/2°E 1.72 US Bearing (Stump) found notch. Maple 12 S41 1/4°W 1.32, Pratt May 13, 1885

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7 Found capped rerod
C/L Road 7' North

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

12 JAN 98 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 Replaced rerod with Barry Co. Mon. (3/4" x 24" Iron Rod with cap)
Set nail & BC Remon tag in NW side P.Pole S50°W 69.61'
Set nail & BC Remon tag in W side sawed off P.Pole N5°W 65.99'
Set nail & BC Remon tag in W. side 14" Willow N20°W 60.21'
Metal culvert marker post NS45°W 49.8'

Signed by

Surveyor's Michigan License No. 39085

Date 11-22-1999

