

SURVEY & REMONUMENTATION

AUG 22 1995

COMMISSION

BARRY COUNTY REMONUMENTATION

STATE OF MICHIGAN COUNTY OF BARRY RECEIVED FOR RECORD

JAN 25 8 34 AM '95

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Sandy Schendelmayr REGISTER OF DEEDS

For corners in BARRY

(County)

Located In: Corner Code #

Table with 3 columns: Description, T/R/S, Corner Code #. Includes 'Public Land Survey W 1/4 CORNER SECTION 7 RUTLAND TOWNSHIP ON RANGE LINE' and 'Property Controlling in Section'.

002273

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36.

BRIAN REYNOLDS 22 OCTOBER 1994

I, BRIAN REYNOLDS, in a field survey on 22 OCTOBER 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1 CORNER NOT SET BY GENERAL LAND OFFICE
2 NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A-5, T3N, R9W, AND M-3, T3N, R10W. RESTORED M-5, T3N, R10W, AND A-3, T3N, R9W. COMPUTED POSITION FOR A-4 AT MID-DISTANCE AND ON RANGE LINE, EXCAVATED AT THAT LOCATION, 1.5' WEST OF EAST EDGE OF GRAVEL ROAD THROUGH 1' OF STABILIZED GRAVEL, 6" OF ROAD SAND, 6" OF BLACK SAND INTO BLACK PEAT, A 4' BY 4' EXCAVATION CENTERED ON COMPUTED POINT, FOUND NOTHING. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AT MID-POINT BETWEEN A-3 AND A-5 ON RANGE LINE.

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON 1 Nov. 1994 BRIAN REYNOLDS COUNTY SURVEYOR



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"X36"W/ALUMINUM CAP) SET 40d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 24" OAK N5°E 157.78' SET 40d NAIL W/PLASTIC TAG IN THE NORTH SIDE NORTH TRUNK OF A 30" MULTI OAK N90°E 8.41' SET 40d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 12" ASH N10°E 43.93' SET 40d NAIL W/PLASTIC TAG IN THE NORTHEAST SIDE OF A 26" TWIN MAPLE S26°E 19.30' 7' EAST OF THE CENTERLINE OF PEETS ROAD 46.64' NORTH OF THE EAST 1/4 CORNER OF SECTION 12, T3N, R10W

Signed by [Signature] Date JANUARY 24, 1995 Surveyor's Michigan License No. 31602