

SURVEY & REMONUMENTATION

AUG 22 1995

COMMISSION

BARRY COUNTY REMONUMENTATION

STATE OF MICHIGAN COUNTY OF BARRY RECEIVED FOR RECORD

JAN 25 8 34 AM '95

Sandy Schendelmayer

REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in BARRY

(County)

Located In: Corner Code #

1. Public Land Survey CENTER OF SECTION 7 RUTLAND TOWNSHIP

Table with columns for Township (T), Range (R), Section (S), and Corner Code (#). Row 1: T 3N R 9W B-4

2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

4. Lot No. , Recorded Plat
5. Private Claims

002270

Register of Deeds Stamp & File Number

I, BRIAN REYNOLDS, in a field survey on 20 OCTOBER, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. A dot is marked at row 4, column B.

A. Description of original monument and accessories and/or subsequent restoration:

- 1 CORNER NOT SET BY GENERAL LAND OFFICE
2 COUNTY SURVEYOR RECORDS: A.N. BATEMAN, MAR 30, 1902 (L.3,P.62), "STAKE SET BY FORMER SURVEYOR"
3 NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND OLD DECAYING FENCES RUNNING EAST-WEST, AND SOUTH. EXCAVATED AT INTERSECTION OF FENCES AND AT 18" BELOW SURFACE, FOUND A CIRCLE OF SMALL STONES MIXED WITH CHARCOAL. UPON FURTHER EXCAVATION FOUND A VERY OLD DECAYING WOOD STAKE (APPROXIMATELY 4" X 20") (OBVIOUSLY NOT A FENCE POST), INSIDE THE CIRCLE OF STONES, WITH A VERTICAL COLUMN OF CHARCOAL ALONG THE WEST EDGE.

REPLACED DECAYING WOOD STAKE WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON

1 NOV. 1994 BRIAN REYNOLDS

BR COUNTY SURVEYOR



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"X36"W/ALUMINUM CAP)
SET 40d NAIL W/PLASTIC CAP IN THE WEST SIDE, NORTHWEST TRUNK OF A 12" MULTI OAK S15°W 10.94'
SET 40d NAIL W/PLASTIC CAP IN THE NORTHEAST SIDE OF A 12" OAK S33°E 31.83'
SET 40d NAIL W/PLASTIC CAP IN THE NORTHWEST SIDE OF A 14" OAK N55°E 11.60'
SET 40d NAIL W/PLASTIC CAP IN THE EAST SIDE OF A 12" OAK N30°W 5.01'
SET 40d NAIL W/PLASTIC CAP IN THE SOUTH SIDE, SOUTH TRUNK OF A 20" TWIN OAK S70°E 47.94'
CORNER LIES 1'+/- EAST OF DECAYED FENCE RUNNING SOUTH
CORNER IS IN LINE WITH DECAYED FENCE RUNNING EAST-WEST

Signed by [Signature] Date JANUARY 24, 1995

Surveyor's Michigan License No. 31602