

**SURVEY & REMONUMENTATION**

APR 26 1995

**COMMISSION**

Barry County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF BARRY  
 RECEIVED FOR RECORD

DEC 8 8 15 AM '94

Sandy Schondelmar  
 REGISTER OF DEEDS

002252

Register of Deeds Stamp & File Number

For corners in Barry (County)	Located In:	Corner Code #/
Public Land Survey	T 3N R 9W	C-6 (E $\frac{1}{2}$ , 18)
	T _____ R _____	Rutland Twp.
	T _____ R _____	
	T _____ R _____	
Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

John C. Bueche, in a field survey on October, 19 94, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:  
 C-6 GLO LCRC #221, Nov., 1977  
 A.W. Oak 12" S 52° E 33 lks. Mon. Box  
 A.W. Oak 14" S 86° W 16 lks. Nail in side 34" Pine SE 44.50'  
 Sylvester Sibley, D.S., 1831 PK in side TP SW 79.53'  
 PK in side PP NW 86.36'  
 Mersnon, no date C/L "X" BT N 3.0' & W 3.0'  
 Set stake, stone & brick

OVER

Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 C-6 Found 1" x 15" solid iron in Mon. Box SE 30" W. Pine C/L 28" Oak N 30° E  
 Nail in side 34" Pine 44.51' 111.5'+  
 SE 44.50'  
 PK in side PP NW 86.36'  
 C/L "X" BT N 3.0' & W 3.0'  
 And is accepted as a careful and faithful perpetuation of the position of the original corner.

ACT 345 BARRY COUNTY REMONUMENTATION  
 APPROVED BY PEER REVIEW AT A MEETING HELD ON

4 Oct. '94  
 BRIAN REYNOLDS COUNTY SURVEYOR

Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 C-6 Replaced solid iron with Std. Barry Co. Mon. (3/4" x 24" Pin with Alum. Cap)  
 Exist. Nail & Tag in SW side 36" Pine S 40° E 44.48'  
 Conc. Nail & Barry Co. Remon. Tag in W side PP S 15° W 180.17'  
 Conc. Nail & Barry Co. Remon. Tag in S side 42" Oak S 75° W 130.75'  
 Conc. Nail & Barry Co. Remon. Tag in NW side 14" Pine N 60° E 94.38'  
 Exist. PK & Tag in NE side PP N 25° W 86.38'  
 C/L "X" of bit. N 3'+, W 3'+  
 Meas. by EDM

Signed by John C. Bueche  
 Surveyor's Michigan License No. 13027

Date 10-26-94



PART A

LCRC #351, March, 1983

1" iron in Mon. Box

SW tel. ped. 79.36'

NE st. sign 61.0'

SE 30" W. Pine 44.51'

NW PP 36.38'

Barry Co. Rd. Comm., Jan., 1973

3/4" pipe in Mon. Box

30" W. Pine, spk. in face S 45° E 42.80'

Face 4" post (Bell tel.) S 65° W 78.85'

Post @ SW cor. hse. roof N 80° E 132.20'

Spk. E side 28" Oak N 30° E 110.90'