

SURVEY & REMONUMENTATION

APR 26 1995

COMMISSION

**Barry County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 8 8 15 AM '94

Sandy Schondalmarer
REGISTER OF DEEDS

002253

Register of Deeds Stamp & File Number

Corner in	Located In:	Corner Code #/
Barry (County)		
Public Land Survey	T <u>3N</u> R <u>9W</u>	<u>C-7 (SE, 18)</u> <u>Rutland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Lot No. _____, Recorded Plat _____
Private Claims _____

John C. Bueche, in a field survey on October, 1994,
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Description of original monument and accessories and/or subsequent restoration:

C-7 GLO	LCRC #351, March, 1983
A.W. Oak 9" N 33° E 75 lks.	1/2" rod
A.W. Oak 16" S 14° W 69 lks.	SW 15" Oak 62.21'
Sylvester Sibley, 1831	NNE 13" Oak 63.24'
	NE 12" Oak 48.30'
	SSE 14" Oak 58.88'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 Found 1/2" rerod
SW 15" Oak 62.21'
NNE 13" Oak 63.24'
SSE 14" Oak 58.88'
And is accepted as a careful and faithful perpetuation of the position of the original corner.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

4 Oct '94 BR
BRIAN REYNOLDS COUNTY SURVEYOR

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 Replaced 1/2" rerod with Std. Barry Co. Mon. (3/4" x 24" Pin with Alum. Cap) 8" below grade
40d Nail & #31602 Cap in SE side 16" Oak S 25° W 62.16'
40d Nail & #31602 Cap in N side PP N 80° W 42.87'
40d Nail & #31602 Cap in W side 14" Oak N 20° E 63.11'
40d Nail & #31602 Cap in E side 20" Oak S 20° E 59.02'
Conc. Nail & Barry Co. Remon. Tag in SW side 12" Pine S 40° E 110.69'
Conc. Nail & Barry Co. Remon. Tag in NE side 10" Elm N 55° E 84.71'
On W edge Rd., on C/L Power Line E-W
Meas. by EDM

Signed by John C. Bueche Date 10-26-94
Surveyor's Michigan License No. 13027

