

SURVEY & REMONUMENTATION

APR 26 1995

COMMISSION

**Barry County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 8 8 15 AM '94

Sandy Schondelmayer
REGISTER OF DEEDS

002251

Register of Deeds Stamp & File Number

For corners in Barry (County)	Located In:	Corner Code #
Public Land Survey	T <u>3N</u> R <u>9W</u>	E-7 (NW, 21)
	T _____ R _____	Rutland Twp.
	T _____ R _____	
	T _____ R _____	
Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Lot No. _____, Recorded Plat _____
Private Claims _____

John C. Bueche, in a field survey on October, 19 94,
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Description of original monument and accessories and/or subsequent restoration:

E-7 GLO	Unrecorded survey
A.W. Oak 10" West 33 lks.	Medema, VanKooten & Assoc.
A.W. Oak 9" N 24° E 15 lks.	#8618, June, 1985
Sylvester Sibley, D.S., 1831	1 1/2" iron pipe
	SE side PP NW 0.63'
	SE side 18" Apple SW 150.12'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7 Found 1 1/2" x 36" pipe SE side PP NW 0.63'

And is accepted as a careful and faithful perpetuation of the position
of the original corner.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

1 NOV. '94
BRIAN REYNOLDS

BR
COUNTY SURVEYOR

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 Placed Barry Co. Mon. (3/4" x 24" Pin with Alum. Cap) inside
1 1/2" pipe
Nail & Barry Co. Remon. Tag in E side PP N 0° E 0.92'
Nail & Barry Co. Remon. Tag in W side 6" Oak N 0° E 53.08'
Nail & Barry Co. Remon. Tag in NW side 6" Apple S 70° W 43.47'
Nail & Barry Co. Remon. Tag in E side 8" Apple S 30° E 97.57'
On Power Line E-W, on old fence N-S
C/L bit. rd. South 466'±

Surveyed by John C. Bueche
Surveyor's Michigan License No. 13027

Date 10-26-94

