

OCT 27 1994

COMMISSION

Barry County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

OCT 4 12 42 PM '94

Sandy Schindelmarer  
REGISTER OF DEEDS

002229

Register of Deeds Stamp & File Number

For corners in Barry (County) Located In: Corner Code #

1. Public Land Survey	T <u>3N</u> R <u>9W</u>	<u>F-7(N<math>\frac{1}{2}</math>, 21)</u> <u>Rutland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John C. Bueche, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-7 1831 Sylvester Sibley D.S.	LCRC #350, March, 1983
A.W. Oak 10" S 10° W 71 Lks	1" pipe
A.W. Oak 9" W 50° E 24 Lks	S 20.78' 4" Ash
1903 Walter Heath	SW 55.57' 4" Maple
Found remains of stake @ intersection	N 65.00' 24" Hickory
Of line fences set stake	C/L power line 0.5' South
(A.W. Oak 10" S 10° W 71 Lks)	On fences N-S-E-W
Hickory 8" N 86 1/2 W 42 1/2 Lks	
Hickory 12" N 2 E 82 3/4 Lks	
Hickory 8" South 31 1/2 Lks	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7	Found 1" pipe
Hickory 12" N 2 E 82 3/4 Lks	As per above wit.
54.62'	

Corner is accepted as a careful and faithful perpetuation of the position of the original corner

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
SEPT. 12, 1994 ISR  
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7 Placed Barry Co. Mon. 3/4" rod & cap inside 1" pipe  
Nail & Barry Co. Remon. Tag in E side 30" Hickory N 05° E 54.92'  
Nail & Barry Co. Remon. Tag in W side 6" Hickory S 10° E 32.38'  
Nail & Barry Co. Remon. Tag in W side 6" Hickory S 45° W 55.50'  
Nail & Barry Co. Remon. Tag in N side PP N 90° E 116.30'  
C/L power line E-W, North 0.5'±

Signed by John C. Bueche  
Surveyor's Michigan License No. 13027

Date Sept 12, 1994  
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

