

SURVEY & REMONUMENTATION

NOV 04 1996

COMMISSION

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

AUG 20 11 27 AM '96

Sandy Schindelmarer
REGISTER OF DEEDS

002401

Register of Deeds Stamp & File Number

For corners in

BARRY

(County)

Located In:

Corner Code #/

1. Public Land Survey	T	<u>3N</u>	<u>R9W</u>	<u>H-1</u>
NORTH 1/4 CORNER OF SECTION 3 RUTLAND TOWNSHIP ON TOWNSHIP LINE	T	_____	R _____	_____
	T	_____	R _____	_____
	T	_____	R _____	_____
2. Property Controlling in Section	S	_____	T _____	R _____
	S	_____	T _____	R _____
3. Miscellaneous Property in Sec.	S	_____	T _____	R _____
	S	_____	T _____	R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, **BRIAN REYNOLDS**, in a field survey on **31 MARCH**, 19**95**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

**CORNER NOT SET BY GENERAL LAND OFFICE.
NO RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER.
CORNER ESTABLISHED (NOT RECORDED) BY BRIAN REYNOLDS, P.S. #31602, 1991, BASED ON OCCUPATION LINES IN SECTION 3, AND TOWN LINE. SET 1/2" IRON
12" ELM N50°W 33.08' 12" BOX ELDER S30°E 21.17' ON CENTERLINE OF EAST-WEST GRAVEL ROAD**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**CORNER MONUMENT AND ALL WITNESSES REMOVED BY ROAD CONSTRUCTION.
RE-ESTABLISHED POSITION FROM 1991 SURVEY. RE-ESTABLISHED POSITION IS NOW IN 8'+ OF NEW ROAD FILL, NEAR LARGE CULVERT.
ACCEPTED AS BEST EVIDENCE OF CORNER POSITION.**



ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
10 April '95 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"X36"W/ALUMINUM CAP)
SET 40d NAIL W/PLASTIC TAG IN THE NORTH ROOT OF A 12" MAPLE S75°W 238.14'
SET 40d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A UTILITY POLE S2°E 60.79'
SET 40d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF A 40" OAK S83°E 261.82'
SET 40d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A UTILITY POLE N26°E 221.56'
SET 40d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 12" TRIPLE MAPLE N36°E 176.17'
CORNER LIES ROUGHLY ON CENTERLINE OF EAST-WEST GRAVEL ROAD
H-13 T4N, R9W, IRVING TOWNSHIP IS EAST 16.85'**

Signed by

Brian Reynolds

Date

August 16, 1996

Surveyor's Michigan License No.

31602