

**SURVEY & REMONUMENTATION**

APR 26 1995

COMMISSION

**Barry County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

DEC 8 8 15 AM '94

Sandy Schondelmarer  
REGISTER OF DEEDS

002256

Register of Deeds Stamp & File Number

corners in	Located In:	Corner Code #
Barry (County)		
Public Land Survey	T <u>3N</u> R <u>9W</u>	<u>I-6 (E<sub>1</sub>, 15)</u>
	T _____ R _____	<u>Rutland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

John C. Bueche, in a field survey on October, 19 94,  
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Description of original monument and accessories and/or subsequent restoration:

I-6 GLO	Co. Rd. Comm.
A.W. Oak 10" S 58° E 30 lks.	Iron Dec., 1970
A.W. Oak 10" N 25° W 10 lks.	36" Oak N 32.3'
Sylvester Sibley, D.S., 1831	18" Oak N 20° E 55.9'
	SE cor. of wall pt. N 30° W 85.0'
	NE cor. of fnd. S 20° W 59.1'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6 Found 3/4" solid iron in Mon. Box  
36" Oak N 32.3'

And is accepted as a careful and faithful perpetuation of the position  
of the original corner.

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

4 OCT '94  
BRIAN REYNOLDS

BR  
COUNTY SURVEYOR

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6 Placed Barry Co. Cap on solid iron  
40d Nail & PS Cap #31602 in W side 46" Oak N 0° E 31.68'  
40d Nail & PS Cap #31602 in SE side 28" Oak N 25° E 56.11'  
40d Nail & PS Cap #31602 in W side 30" Oak S 20° W 53.44'  
SE cor. hse. #3002 fnd. N 50° W 108.22'  
Field division N & S, on C/L bit. E-W

igned by John C. Bueche  
Surveyor's Michigan License No. 13027

Date 10-26-94

