

DEC 7 2 04 PM '93

Sandy Schondelmayer
REGISTER OF DEEDS

Barry County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Barry
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>3N</u> R <u>9W</u>	<u>I-7 (SE, 15)</u>
	T _____ R _____	<u>Rutland Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

002100

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1. John C. Bueche in a field survey on March, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-7 LCRC #289, Feb., 1980
1" iron
Face Tw. 26" Maple N 50° E 72.2'
Face Tw. 12" Maple N 25° E 53.5'
Face Tw. 19" W. Cherry N 48.6'

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-7 Found 1" x 30" iron @ fence cor. E-W & S
As per above wit.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7 Replaced 1" x 30" iron with Std. Barry Co. Mon. (3/4" x 24" pin with alum. cap)
Nail & B.C. Remon. Tag in W side 10" Ash N 25° W 57.17'
Nail & B.C. Remon. Tag in E side 28" W. Cherry N 05° E 49.47'
Nail & B.C. Remon. Tag in E side dbl. 20" Maple N 55° E 72.98'
Nail & B.C. Remon. Tag in W side dbl. 18" Maple N 30° E 54.26'
Nail & B.C. Remon. Tag in E side. 6" Oak S 0° E 31.61'
At fence cor. E-W & S
On power line E-W

Signed by John C. Bueche

Date Oct 29, 1993

Surveyor's Michigan License No. 13027

