

SURVEY & REMONUMENTATION

APR 26 1995

COMMISSION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
REGISTERED FOR RECORD

Nov 22 3 43 PM '94

Sandy Schmalzberger
REGISTER OF DEEDS

002242

Register of Deeds Stamp & File Number

For corners in

Rutland Township

Barry
(County)

Located In: Corner Code #

1. Public Land Survey	T	<u>3N</u>	R	<u>9W</u>	<u>L-10</u>
	T		R		<u>Center of</u>
	T		R		<u>Section 25</u>
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Chris Marschall, in a field survey on August 8, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

6. Description of original monument and accessories and/or subsequent restoration:

Fd. @ intersection of 1/4 lines (1875)
28" Oak S45°W 13'
10" Beech N68°E 23'
Found 1890

7. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Nothing
Set Standard Barry County monument at the intersection of the 1/4 lines

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

7 June '94 BR
BRIAN REYNOLDS COUNTY SURVEYOR

8. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 Standard Barry County Monument (3/4" Iron) with Aluminum Cap
Nail and Tag in the E side 8" Ash N1°30'E 48.68'
Nail and Tag in the W side 8" Walnut N30°20' W 65.58'
Nail and Tag in the N side 12" Hickory S62°40"W 68.49'
Nail and Tag in the N side 22" Oak S66°10'E 52.15'
Centerline of E-W Gravel Road North 6'±



Signed by Chris Marschall Date August 8, 1994

Surveyor's Michigan License No. 18661