

1993

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

JUL 20 11 28 AM '93

COMMISSION

Sandy Schondelmayer
REGISTER OF DEEDS

For corners in

BARRY

(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 3N R 9W M-9
 T _____ R _____ RUTLAND TWNSP.
 T _____ R _____ TWNSP. LINE COR. SEC. 24 & 25
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

002057

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

BRIAN REYNOLDS

JUN

93

I, BRIAN REYNOLDS, in a field survey on _____, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.:

**BEECH 11 S53W 8
BEECH 5 N52W 19**

LEE COBB (BOOK IX)(1892)

**FOUND ONE U.S. TREE:
BEECH 5 N52W 19**

SET LIMESTONE 28 x 8 x 5 & BRICK

REYNOLDS: (1992)

FOUND LIMESTONE;

**36" OAK - S. - 7.70'
20" TWIN ASH - N30E - 74.83'
6" MAPLE - N05W - 33.00'
E. - W. FENCE - N. - 32.3', TREE ROW S.**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 36" x 6" x 4" LIMESTONE WITH DRILL HOLE & BRICK.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET BARRY Co. REMON. MONUMENT, SURROUNDED WITH THREE LARGE STONES:

REYNOLDS' PREVIOUS WITNESSES PRESENT AND CHECKED.

S. FACE - 5" BLACK WALNUT - S88E - 25.61'

W. SIDE - WOODEN FENCE POST - N44W - 39.39'

(40 D NAIL WITH SHINER FOR WITNESS)

Signed by



Date

7-13-93

Surveyor's Michigan License No.

31602