

SURVEY & REMONUMENTATION

APR 26 1995

COMMISSION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED

NOV 22 3 43 PM '94

Sandy S. Sundelander
REGISTERED DEEDS

002243

Register of Deeds Stamp & File Number

Barry (County)	Located In:	Corner Code //
Public Land Survey	T 3N R 9W	M-10
	T _____ R _____	E 1/4 Corner
	T _____ R _____	Section 25
	T _____ R _____	
Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Lot No. _____, Recorded Plat _____
Private Claims _____

Chris Marschall, in a field survey on August 8, 1994,
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Description of original monument and accessories and/or subsequent restoration:

<u>GLO Set Stake @ 40 Ch.</u>	Beech 20	S77W 50
	Beech 16	N57W 39
Stone and Brick	No Date	
6" Butternut	S73W	20.5
7" Elm	N13E	40'
20" Beech	S77W	50'
16" Beech	N57W	39'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Nothing down to 5 feet
Set Standard Barry County Monument
Midway and on line between NE and SE corner of Section 25

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
7 June 1994
BRIAN REYNOLDS COUNTY SURVEYOR

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 Standard Barry County Monument (3/4" Iron) with Aluminum Cap.		
Nail and Tag in SW side Twin 8"-12" Oak	N30°W	72.64'
Nail and Tag in W side Twin 10" Oak	N25°E	63.02'
Nail and Tag in S side Twin 34" Butternut	N85°E	25.37'
Nail and Tag in W side PP	S10°W	98.55'
Intersection of Hall and Cook Roads	North	175'±



Signed by Chris Marschall Date August 8, 1994
Surveyor's Michigan License No. 18661