

- |     |      |  |
|-----|------|--|
| X   | 9    | See line between 3 & 4 Found 1 1/2" iron pipe with 90° ell on top  |
| 6   | 10.5 | 1" x 1' x 6" rock (1960)   |
| 6   | 11   | See line between 3 & 4 set 1" pipe with brass cap 8" below road<br>N45E, 58.62', 8" walnut; N52°W, 49.84', 30" twin red oak;<br>S42°30'E, 74.6', N.W. Cor of house. (1960)                                       |
| 2   | 5    | West 1/4 cor sec 20 stone & stake - N34 1/2° E, 48.8' 24" oak; N30°W, 53.9' 10" oak;<br>S9°W 29.7' 14" walnut; W.C. standard monument N44°44'E, 47.56'   |
| 2   | 6    | Section Cor 17/18, 1920, 1 1/2" iron 5 ft high. SW 13.7' oak 35"; SE 57.4 oak 20"  |
| 4   | 5    | East 1/4 cor sec 20 iron set in concrete located in the diamond formed by the<br>roads and level with the surface of the ground  |
| 3.5 | 5    | N.W. cor of NE 1/4 of SE 1/4 section 20 2" iron with bridge spike in top end<br>located at the intersection of Briggs and Mety roads; S30°E 92.1' 6" oak;<br>N45°W 74.9' 32" wild cherry; N45°E 64.0' 10" maple. |