

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 3N N.R. 10 W


BARRY COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 28 & 29

CORNER MONUMENT Standard bronze cap in 1" x 24" pipe

DATE MONUMENT PLACED AND WITNESSED \_\_\_\_\_

WITNESSES TO CORNER..... 30" Beech N36E 47.5'



10" White Oak N87E 13.4'

10" White Oak S 8 E 11.65

10" Oak S32W 19.05'

AND

CIRCLE CORNER REGISTERED A pine stump due west 3.0' (possibly original 1/4 corner)

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner restored from monument established by U.S. Government, marking property boundary - and from center of Section 29 as found in the field, and running line north to Long Lake (originally called Gun Lake in G.L.O. notes)

SURVEYOR'S SEAL

SIGNED

*James J. Ford*  
REGISTERED LAND SURVEYOR

DATE

April 1962