

**Barry County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Barry

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|----------------------------|
| 1. Public Land Survey | T <u>3N</u> R <u>10W</u> | <u>I-13 (SE, 34)</u> |
| | T ___ R ___ | <u>Yankee Springs Twp.</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling
in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous
Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John C. Bueche, in a field survey on September, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration.

I-13 GLO	Barry Co. Rd. Comm., does not state
W. Oak 14" N 65° E 50 lks.	what was there, 1950
W. Oak 8" N 81° W 68 lks.	26" R. Oak N 71° W 41.5'
	48" B. Oak N 21° E 26.3'
Bowen, 1875	
Stone	LCRC #191, Jan., 1976
B. Oak 10" N 53° E 52 lks. (34.32')	1 1/2" solid iron rod
W. Oak 6" N 70° E 100 lks. (66')	S 36° E 24.20' 8" Oak
	S 21° W 19.38' 5" Oak
	N 87° W 42.75' 32" Oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I-13 Found large stone 10" dia. x 20" deep, referenced by Bowen, 1875 which checks ALLEN'S ACRES SUB., recorded in Feb., 1962
Found 1 1/2" pipe 12'± South & 11'± West, LCRC #191
Found 1 1/2" pipe 11'± South & 4'± West
And is accepted as a careful and faithful perpetuation of the position of the original corner.

*Scotts
works
to lay
moored*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

I-13 Replaced stone with Barry Co. Mon. (3/4" x 24" Pin with Cap) on top 3/4" x 24" Pin
Nail & Barry Co. Remon. Tag in N side 24" Oak N 90° E 59.44'
Nail & Barry Co. Remon. Tag in NW side 14" Oak N 60° E 33.78'
Nail & Barry Co. Remon. Tag in E side 10" Oak S 25° E 55.67'
Nail & Barry Co. Remon. Tag in W side 12" Oak S 25° W 48.33'
Nail & Barry Co. Remon. Tag in E side 6" Oak S 55° W 66.50'
N edge of 2 track E-W, South 12'±
C/L bit. (Yankee Springs Rd.) West 520'±
1 1/2" pipe 12'± South & 11'± West
1 1/2" pipe 11'± South & 4'± West

Signed by

John C. Bueche

Date 10-26-94

Surveyor's Michigan License No

13027