

BARRY

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>33-34</u> , T. <u>3</u> N. <u>3</u> , R. <u>10</u> E. <u>10</u> W.		<u>I-13, E-13, I-12</u>
2. PROPERTY CONTROLLING IN SECTION <u>33-34</u> , T. <u>3</u> N. <u>3</u> , R. <u>10</u> E. <u>10</u> W.		<u>G-13, G-12</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S. _____, R. _____, E. _____, W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Dwayne Scott, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on December, 1975, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- SE 34 I-13 Recovered 1-1/2" Solid Iron Rod, N. Edge Dirt Road
- SW 33 E-13 Recovered 1/2" Iron Rod in Conc., Rod is 3" above ground in fence corner with fences going N. and E., Plastic Cap #12029
- E 1/4 34 I-12 Recovered 1-1/2" Iron Pipe in Conc. 10" below ground, found with Metal Detector, Placed 3/4" pipe inside 1-1/2" pipe and Cap #12029 raised to surface.
- SW 34 G-13 Set 4" x 30" Conc. Mon. w/alumn. cap, Set Cor. on Twp. line and single prop. Dist. from Sec. Cors. E. and W.
- W 1/4 34 G-12 Set 4" x 30" Conc. Mon. w/alumn. cap, Set according to Gov't ties to the north and line of Occ. to the East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|--|--|--|
| 1 ✓ I-13 1-1/2" Solid Iron Rod
S36°E 24.20' 8" Oak
S21°W 19.38' 5" Oak
N87°W 42.75' 32" Oak | 4 ✓ I-12 1-1/2" Iron Pipe in Conc. w/3/4" pipe and Cap #12029
S43°W 71.81' 12" B. Oak
N47°E 36.3' SW Cor. David B. Watson headstone in cemetery.
S74°W 6.0' 48" B. Oak Stub 16' high
S83°E 25.44' 52" B. Oak | 2 ✓ G-13 4" x 30" Conc. Mon. w/alumn. cap
N47°W 28.55' 19" B. Oak
S61°W 35.84' 14" W. Oak
N10°E. 14.70' 6" B. Oak
East 16.5' Conc. Mon. NW Corner Sec. 3 |
|--|--|--|
- 5 ✓ E-13 1/2" Iron Rod in Conc. Plastic Cap #12029
S03°E 17.59' 19" W. Oak
S86°W 25.47' 46" B. Oak
S36°E 19.68' 14" W. Ash
East 48.35' NW Cor. Sec. 4, T2N, R10W
- 3 ✓ G-12 4" x 30" Conc. Mon. w/alumn. cap
S80°W 35.32' 20" Box Elder
N49°E 38.82' 18" Oak
S42°E 35.98' 16" Oak

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY [Signature] CHIEF OF SURVEY PARTY DATE Jan 1976
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 12029