

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Barry

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>10W</u>	<u>G2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Gary C. Bilow, in a field survey on June 22, 1992, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G2: Post established by U.S. Deputy Surveyor S. Sibley in 1831 - accessories: W. Oak 10, S41W 28 links and W. Oak 7, N43E 37 links. County Surveyor A.D. Rork in 1866 records in County Survey Records "bearing found Stone and Earthen in post hole." W. Paddison (LS #7256) reestablished corner in 1960 as "Set 4" Brass cap on 1" iron pipe midway between East-West 1/8 lines to the North and South and at the intersection of a road to the North with an East-West road - accessories: N45E 58.62', 8" Walnut; N52W 49.84', 30" Twin Red Oak; and S42.5E 74.6', NW corner of house." Corner recorded under Act 74 PA 1970 by D. Bonnema (LS #12579) in Liber 1 Page 220 as "Found 4" Brass Cap from previous witnesses - accessories: Nail in sde P. Pole, SW 54.18'; Nail in sde 24" Twin Oak, NW 49.83'; Nail in sde 12" Walnut, NE 58.53'; and NW cor hse fndn. SE 74.42'."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 G2: Found 1" pipe .8" deep at the intersection of a road to the North with an East-West road and two (2) of Bonnema's witnesses. Accepted this corner as the best evidence of the original GLO post.

G2: Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Found 1" pipe
 SW 54.18', Nail & Tag in Power Pole
 SE 74.42', NW corner House foundation
 NW 47.1', Sign post
 N41E 74.29', Spike in 12" Walnut



Signed by Gary C. Bilow Date 12/7/92
 Surveyor's Michigan License No. 26453